



# Implementing Lean Construction at CBI's Largest Brewery



Health precautions to keep everyone as safe as possible at Congress:

- Wear masks at all times in indoor events.
- Complete your daily health screening on your phone and bring it with you when you enter the center each day.
- Practice social distancing to the extent possible. Seating at plenary sessions is structured to help with this.
- If you feel ill at any time, please leave the conference and return to your room/consult a physician as necessary.
- Ultimately, our collective health and safety at Congress is up to all of us. Thanks for your support!



#### Presenters



Jose Serrano Project Director

Constellation Brands, Inc.

jose.serrano@cbrands.com



Jose Garcia
Executive Sponsor

Gilbane Alberici Mexico

Jose.Garcia@alberici.com



Manuel Zepeda Superintendent

Gilbane Alberici Mexico

Manuel.zepeda@alberici.com



Brett Friedel Site Superintendent

Gilbane Alberici Mexico


Brett.friedel@alberici.com



# The Background



#### Nava Project Timeline



#### INSTALLED BREWERY CAPACITY

30MHL
(Annual Capacity)

16

Packaging Lines (4 Cans, 2 Kegs, 10 Bottles) 26,000

Bottles per Minute at Capacity (2,600 per line) 3,200

Cans per Minute at Capacity (800 per line)

#### **CONSTRUCTION SAFETY**

Peak On-Site

Labor

Nava 5143 Mexicali 1900 Obregon 2820 **Total Work Hours** 

41.3M

Nava 26.6M Mexicali 8.9M Obregon 5.8M **Lost Time Incidents** 

17

Nava 8 Mexicali 5 Obregon 4 LTIR

.082

LTIR is ranked among the top performers in the industry







# The Opportunity



#### The Opportunity

- After 7 years of successful construction projects, including building CBI's largest brewery, the Team wanted to continue to push the envelope of what's possible in terms of safety, quality, schedule and cost:
  - Avoid Complacency
  - Continue to Innovate
  - Continue to Improve



12

#### Brewery Expansion - Nava, Coahuila, Mexico



**Seltzer Process Building** 

**Packaging Expansion** 

New BBT's

# Our Approach



#### The Lean Edge Program







Team Building & Alignment



Conditions of Satisfaction (CoS)



Big Room





Facilitation, Coaching & Training


# 1 | Team Building & Alignment



## Team Building & Alignment



#### Team Building & Alignment






18

© LEAN CONSTRUCTION INSTITUTE

#### Team Building & Alignment





© LEAN CONSTRUCTION INSTITUTE 19

# 2 | Conditions of Satisfaction



LEAN**EDGE>** 

**NAVA CHS PROJECT** 

#### **CONDITIONS OF SATISFACTION**

#### SAFETY

- » Zero recordable incidents
- » Streamline process for personnel access 2 days vs. 7 days or more. Review and communicate the process.

#### ONE TEAM

- » Take at least one team satisfaction survey per quarter
- » Have a common understanding of expectations

#### • RFIs

» Submit all RFIs with clear priority information (not ALL can be highest priority)



#### • COMMUNICATION / INFORMATION SHARING


- » Strong communication: we are all on the same page to enable efficient workflow. Clear and open communication between safety, superintendents, and PM's.
- Immediately communicate changes to the whole team – daily field handoff of information.

#### • SCHEDULE


- » Everyone is committed to being on time every day to reduce impact on each other's schedules and the overall project productivity
- » Make reliable promises commit to tasks
- » Work as a team to overcome schedule challenges, regardless of where they originated

# 3 | Big Room


## Big Room





## Big Room



#### Big Room


















© LEAN CONSTRUCTION INSTITUTE 28





29


© LEAN CONSTRUCTION INSTITUTE






© LEAN CONSTRUCTION INSTITUTE 31

Gilbane Alberki			Constellation Brands	SP   Semana   SE   No.   No.		Projecto STA ACESTA ACESTA ACESTA ACESTA ACESTA COREY COREY COSAR OT OTTO (Describe)		PLAN DE TRABAJO SEMANAL <sub>V3.0</sub> W40  CHS-Nava Project													100						
LEAN <b>EDGE&gt;</b>		SO W39 PL W40 OMIMaterial		1072				ntaje de Avance	de Avance 77 10/8 10/9 10/10			Man Pow		an Power	er		Razones de NO cumplimiento			ento		Terminado					
-	S <sub>→</sub> ↑ F	ot. A	AREA ▼	BP ▼	Compañía — Responsable	DESCRIPCION DE LA ACTIVIDAD			M ~				Person — Responsa	~	<b>-</b>	<b>-</b>		<b>V</b>	<b>-</b>   -	-		-	RC-Seman ▼		R w	COMENTARIOS	
1	W32		17A	26A.01	GRICO	Acondicionamiento de área para ingresar con plataformas de elevación	100%						Salvador ixta	8			1		×			T		х			Acondicionamiento de ár
2	W32	PKG	17A	26A.01	GRICO	Fabricación de soportes para toma		25%	50%	75% 100%	:		Salvador lista		8 8	8 8			×	OE	OE		oq		×	Estan pendientes detalles de pintura, ya que las piezas no se dejaron secar lo suficiente	Fabricación de soportes
3	W32	PKG	17A	26A.01	GRICO	Instalación de soportes			25%	50% 75%	100%	٤ -	Salvador lixta		8	8 8	8			OE	OE		OQ.		×	Estan pendientes detalles de pintura, ya que las piezas no se dejaron secar lo suficiente	Instalación de soportes -
4	W32	UTL	Rack P	03H.00	COSAR	Excavación en zapata P6 de rack	50%	100%					Octavio González											×			Excavación en zapata P6
5	W32	UTL	Rack P	03H.00	COSAR	Demolición en zapata P6 de rack			30%	60% 90%			Octavio González											х			Demolición en zapata P6
6	W32	PKG	17B	31A.04	COSAR	Colocación de sub-base eje 6-8	50%	100%					Octavio González					- 1	CL SC	)				×			Colocación de sub-base
7		PKG	18C	03B.00	COSAR	Relleno en Truck Dock	70%	75%	80%	85% 100%	•		Octavio González						PL PI	. PL	PL		PL		×	Se quedó en un 77%	Relleno en Truck Dock - 1
8	W32	PKG	PRECAST	05B.02	COSAR	Colocación de muro pre-colado eje FX	17%	27%	37%	47% 57%	67%		Octavio González	8	8 8	8 8	8		x s	X	PL		SI		×	Interferencia con los trabajos realizados por la roladora de Acesta	Colocación de muro pre-
9	_	-	CTO ELECT.	03B.00	COSAR	Escarificado de base para equipo	30%	_	100%				Octavio González	_	3 3				x x	_				х		Existio un campio en el diseno del material	Escarificado de base para
10	W32		CTO ELECT.	03B.00	COSAR	Perforación para varillas en muro	30%		_	100%		$\perp$	Octavio González	_		3			x GI	GD	GD		GD		×	(block) y se tuvo que esperar la aprobación	Perforación para varillas
11	W32		CTO ELECT.	03B.00	COSAR	Barrenos para base	30%	70%	100%				Octavio González	3	3 3									X		EXISTIO UNI CAMBIO en el DISENO DEI MATERIAL	Barrenos para base - 100:
12	W32		CTO ELECT.	03B.00	COSAR	Anclaje de varillas			30%	70% 100%	:	$\perp$	Octavio González			3 3	3			1			GD		×	(block) y se tuvo que esperar la aprobación	Anclaje de varillas - 100%
	W32	_	18B	21A.00	HB	Instalación de soportería eje FX del 8-5	44%						Miuguel Reyes											×			Instalación de soportería
14	W32		18C	21A.00	HB	Instalación de soportería eje FX del 5-3X		60%					Miuguel Reyes											×			Instalación de soportería
15	W32		18C	21A.00	HB	Instalación de soportería eje 3X del FX-EX			70%				Miuguel Reyes											X			Instalación de soportería
16	W32	$\rightarrow$	17C	21A.00	НВ	Instalación de soportería eje 3X del FX-EX				80%			Miuguel Reyes										SI		×	Interferencia con el material de Acesta	Instalación de soportería
17	W32	-	18A	21A.00	HB	Instalación de tuberia de 12"				7%			Miuguel Reyes											×			Instalación de tuberia de
18		PKG	17A	21A.00	НВ	Instalación de soportería eje 14 del EX-DX					100%	4	Miuguel Reyes											Х			Instalación de soportería
19	W32	_	17C	22B.00	IMEC	Habilitado de casquillos y soportes pluviales eje EX		10%		40% 60%	80%		Jorge Vences	8	8 8	8 8	8		× ×				GD		×	Se quedó en un 40% debido al cambio de material (cople)	Habilitado de casquillos
20	W32	_	17A	03D.00	PROSSESA	Colocación de base hidraulica Fase n* 1			100%				Oscar Garcia											Х			Colocación de base hidr
21	W32	-	17A	03D.00	PROSSESA	Colocación de base hidraulica Fase n* 2				100%			Oscar Garcia							-				х			Colocación de base hidr
22		PKG	17A	03D.00	PROSSESA	Colocación de base hidraulica					100%	٤	Oscar Garcia											Х			Colocación de base hidr
23	W32		18A	03D.00	PROSSESA	Colado losa floteada #38		100%					Oscar Garcia											×			Colado losa floteada #3
	W32	-	18A	03D.00	PROSSESA	Colado losa floteada #39			100%				Oscar Garcia											Х			Colado losa floteada #3
25	W32		18A	03D.00	PROSSESA	Colado losa floteada #40				100%		4	Oscar Garcia											Х			Colado losa floteada #4
	W32	_	18A	03D.00	PROSSESA	Colado losa floteada #41				100%			Oscar Garcia											X			Colado losa floteada #4
27	W32	-	18A	03D.00	PROSSESA	Colado losa floteada #42		-	-		100%	4	Oscar Garcia					_		-				×		La cuadrilla del concreto se encontraba de	Colado losa floteada #4
28	W32	-	18C	03D.00	PROSSESA	Colado losa pulida #18	100%					+	Oscar Garcia				+		OP		+++	$\perp$	OP		×	rotación por lo que solo se encontraba de rotación por lo que solo se colocó el acero La cuadrilla del concreto se encontraba de	Colado losa pulida #18 -
29	W32	-	18C	03D.00	PROSSESA	Colado losa pulida #15	+	100%				+	Oscar Garcia					$\dashv$	OF			+	OP		×	rotación por lo que solo se colocó el acero La cuadrilla del concreto se encontraba de	Colado losa pulida #15 -
30	W32	_	18C	03D.00	PROSSESA	Colado losa pulida #19	-		100%	400		+	Oscar Garcia	_			+	$\dashv$		OP		$\perp$	OP		×	rotación por lo que solo se colocó el acero La cuadrilla del concreto se encontraba de	Colado losa pulida #19 - 1
31	_	PKG	18C	03D.00	PROSSESA	Colado losa pulida #21	-	400		100%		+	Oscar Garcia				+			-		$\perp$	OP		×	rotación por lo que solo se colocó el acero Los superintendentes cambiaron las áreas	Colado losa pulida #21 - 1
32	W32	_	17A	33B.00	ADEIDSA	Excavación de zanja D2		100%			-	+	Marco Valles				+	_			++	+	GG		×	de trabajo (prioridades)	Excavación de zanja D2 -
33	W32	_	17A	33B.00	ADEIDSA	Habilitado de tuberia D1	100%					+	Marco Valles							1		+		х			Habilitado de tuberia D1-
34	W32	_	17A	33B.00	ADEIDSA	Retiro de material producto de excavación	100%					+	Marco Valles				+	-			++	+		×		Los superintendentes cambiaron las áreas	Retiro de material produc
35	W32	-	17A	33B.00	ADEIDSA	Instalacion de tuberia, acostillamiento, relleno y compactado D2	+	100%	100-		-	+	Marco Valles				+	$\dashv$				+	GG		х	de trabajo (prioridades)  Los superintendentes cambiaron las áreas	Instalacion de tuberia, aco
36	W32		17A	33B.00	ADEIDSA	Excavación D1	+	50%	100%		-	+	Marco Valles				+	$\dashv$				+	GG		×	de trabajo (prioridades)	Excavación D1 - 100%
	W32	_	17A	33B.00	ADEIDSA	Instalación de tuberia D1	+	-	100%		-	+	Marco Valles	_			+	$\dashv$	+			+		×		Los superintendentes cambiaron las áreas	Instalación de tuberia D1
38	W32		17A	33B.00	ADEIDSA	Relleno de fluido D1 y D2	+	-	100%	100*4	-	+	Marco Valles				+	+	+			+	GG		X	de trabajo (prioridades) Los superintendentes cambiaron las áreas	Relleno de fluido D1 y D2
40	W32	_	17A	33B.00	ADEIDSA	Exacavación (7-8) (C2-D1)	+	-	-	100%		+	Marco Valles	+				$\dashv$	+	+		+	GG		×	de trabajo (prioridades)  Los superintendentes cambiaron las áreas	Exacavación (7-8) (C2-D1
	_	-	17A	33B.00	ADEIDSA	Excavación C2	+	-		50% 100%	•	+	Marco Valles	-				+	_	+		+	GG		×	de trabajo (prioridades) Los superintendentes cambiaron las áreas	Excavación C2 - 100%
41	W32	PKG	17B	33B.00	ADEIDSA	Retiro de material producto de excavación				100%			Marco Valles										GG		×	de trabajo (prioridades)	Retiro de material produc






## 5 | Facilitation, Coaching & Training



## Facilitation, Coaching & Training



### Facilitation, Coaching & Training



#### LEAN**EDGE>**

#### Course Duration - 2.5 hours

Welcome to Lean Edge Training. In this course, we will discuss the concepts of Lean Construction, an overview of the Lean Edge Program and the additional tools that aid in Lean implementation.


Proprietary Information Acknowledgement

- Introduction
- Introduction to Lean Construction
- Lean Edge
- Team Building & Alignment
- Conditions of Satisfaction
- Big Room
- Last Planner System®
- Facilitation, Coaching & Training

#### ADDITIONAL TOOLS

- Additional Tools
- Gemba Walk
- Off-Site Construction
- Plus / Delta
- Conclusion


## Facilitation, Coaching & Training





© LEAN CONSTRUCTION INSTITUTE 38


## Facilitation, Coaching & Training





# Lean Edge Program | Additional Tools: Prefabrication Case Study


















# Our Lean Journey


#### Trade Partners Stepped Up

- Despite little previous experience, trade partners embraced LPS by "doing" it.
- Encourage ownership: it's their meeting.

 Daily Huddles got quicker & better by letting them establish their own rules (e.g. hold meetings in the

field).








#### The Sooner the Better

 Engage trade partners in pull sessions as soon as they're contracted on the project (don't wait for them to mobilize onsite to do actual work for the planning to begin).



#### PPC Reports: Focus on Coordination

- At first, when trades reported information different than what was previously committed, the team spent more time checking and comparing the information than coordinating the work.
- We created a dynamic data base tool to make updates easier and faster and have information available for weekly and monthly reports and make decisions about trade partner status.



# Pluses

#### What Went Well

- Project is on track and on budget with outstanding safety performance
- Owner's commitment and support
- GAM executive sponsorship support from top down
- Virtual Lean trainings & kickoffs (Covid)
- Consultants on site to support implementation
- Effective Big Room set-up
- LPS implementation daily huddles
- Subcontractor buy-in receptive to Lean practices
- Reliable field results
- Flexibility to adjust for better outcomes

# Deltas

#### What Can be Improved

- Establishment of a Lean Culture and Mindset
- Team building & alignment intermediary milestones, procurement, critical path vs non-critical path activities
- Conditions of Satisfaction development / implementation
- Facilitation, coaching & training
- Too few were involved need to spread the workload
- Better English/Spanish communication bilingual teams
- Trade partners' executive support
- Better integration between P6 scheduling and LPS
- Celebrate success more!

## What's Next?

#### What's Next?

- New CBI Phase of Construction in Obregon, MX
- We're Doubling Down:
  - Onsite Project Lean Steering Committee
  - Digital Pull Planning
  - Updated Training Virtual and In-Person
  - More Frequent Feedback and Adjustments (Surveys, Plus/Delta, etc.)



# How Can You Apply This Tomorrow?



#### How Can You Apply This Tomorrow?

- Secure Commitment and Support at the Highest Level
- Early engagement Start Early
- Have a Program Get external help if need to develop one
- Include the right people Lean Champions: passionate and influencers
- Lean out Your Practices: Less in More Focus on What Adds The Most Value
- Consider unique cultural settings: language, culture, union/non-union, etc.
- Highly Dynamic Project Be Flexible
- Expect the Unexpected & Adapt COVID
- Leverage Technology Virtual meetings, online training, digital tools
- Patience: it's a journey! Expect skepticism. Don't Give Up.





In the spirit of continuous improvement, we would like to remind you to complete this session's survey! We look forward to receiving your feedback.



#### Contact Us



Jose Serrano Project Director

Constellation Brands, Inc.

jose.serrano@cbrands.com



Jose Garcia
Executive Sponsor

Gilbane Alberici Mexico

Jose.Garcia@alberici.com



Manuel Zepeda Superintendent

Gilbane Alberici Mexico

Manuel.zepeda@alberici.com



Brett Friedel
Site Superintendent

Gilbane Alberici Mexico

Brett.friedel@alberici.com







