

Lean Collaboration and Involvement from the Owner's Perspective

James Pease, UCSF Health
John Zachara, Integrated Facilities Solutions, Inc.

LEARN BY DOING FROM THOSE WHO DO
October 20, 2021

Health precautions to keep everyone as safe as possible at Congress:

- Wear masks at all times in indoor events.
- Complete your daily health screening on your phone and bring it with you when you enter the center each day.
- Practice social distancing to the extent possible. Seating at plenary sessions is structured to help with this.
- If you feel ill at any time, please leave the conference and return to your room/consult a physician as necessary.
- Ultimately, our collective health and safety at Congress is up to all of us. Thanks for your support!



Our Presentation Team

James Pease

UCSF Health

james.pease@ucsf.edu



John Zachara

Integrated Facilities Solutions, Inc.

jzachara@ifspm.com




Problem Statement(s)

- 1.Lean is not a 4-letter word
- 2. Core Values Alignment
- 3. Validation Outcome Certainty
- 4. Transparency
- 5. Coaching for Owner's

What Owners Should Know About Projects



You Can't Buy a Building Like A Car



© LEAN CONSTRUCTION INSTITUTE 6

Consumers Can Shop & Compare Cars

- Price (budget)
- Availability (schedule)
- Features (scope)
 - Gas Mileage (or no gas)
 - Capacity (# of seats)
 - Top Speed (fast)
 - Leather Seats (premium)




Building a car, the way we build buildings?

Consumers Can Shop for Cars

- Start the design from scratch
- Hire the cheapest companies
- Order parts from 100's of vendors
- Get them delivered to your garage
- Let everyone start building at once

Then wonder why it takes longer, costs more and you don't get what you wanted....




Lean is not a 4-letter word




Project Master Phase Planning









Design for Fabrication not for Intent












Risk Assessment and Tracking





Item N	Risk/Opportunity Description	Assessed Risk	Accepted.	Rejected	BIC ,	Actions Required for Approval	Pros	
1.01	Delay start of project until spring to avoid winter conditions	- I I I I I I I I I I I I I I I I I I I		(20,000)	REJECTED	Rejected - Provides little savings and unacceptable push in schedule		1 1 1 1 1 1 1 1 1
3.01	Eliminate Roof Deck Concrete			(78,000)	REJECTED	Rejected - Would cause too much future cost should the 2nd floor go forward. The savings would also likely be less due to additional structural		
.01	Concrete additive in lieu of surface applied moisture mitigation for flooring			0	REJECTED	Researched Ardus concrete additive. Works out to \$5.50/sf in additional cost. Not competitive with moisture mitigation. Recommend rejecting.		
.01	A - Provide alternative brick - Glenn Gary	(3,050)			APPROVED	John review with Northshore. John to get pictures of sample projects.		
4.01	B - Provide alternative brick - General Shale	(6,510)			REJECTED	projects.		
4.01	C - Provide utility versus modular bricks - IL Brick	(34,000)			REJECTED	John review with Northshore. Mike S. to send John pictures of sample projects. Brick samples to arrive Tuesday at IFS main office.		
4.02	Provide cast stone or precast in lieu of limestone brick and remove limstone between windows.				REJECTED	Mike and Jeff to work together to define scope and price of reduction in the amount of limestone in the project		
5.01	Substitute composite roof deck with standard roof deck 3" N20 ga.			(\$4,000)	REJECTED	Rejected - 2nd Story is required. Check hangers requirements, envelope	Cost savings.	N/A if keeping 2nd
5.02	Substitute composite roof deck with standard form deck.			(\$4,000)	REJECTED	Rejected - 2nd Story is required. Check hangers requirements, envelope	Cost savings.	N/A if keeping 2nd
5.03	Eliminate 6" 18-gauge metal studs and in-wall R-19 batt insulation with kraft facing/vapor barrier, replace with 3 5/8" 18-gauge metal studs at perimeter wall conditions of building.		(2,000)		APPROVED	3.5" polyiso rigid insulation in lieu batten insulation with 3 - 5/8" studs.	Keeping the insulation and vapor barrier on the exterior of the perimeter walls and not within the stud cavities will give a more efficient envelope and allow for future renovation to occur within the stud walls, such as moving walls and outlets, to occur without	No issues.



Core Values Alignment


Core Values/Culture






Core Values/Culture





Core Values/Culture



Culture





Validation – Outcome Certainty



Validation


Can We Deliver the Proposed Program and **Quality** within the Schedule and Budget Supported by the **Project's Business** Case?



Ensuring Success

Cost Certainty

- Cost Benchmarking and Baselining
- Consistent Management and Oversight Staff
- Trade Partner
 Continuation from one
 Project to the Next




American Family Insurance - Validation

Traditional Process:

- 13-14 months
- \$5M-\$6M design fees
- Value EngineeringWaste (redesign)

Lean Validation Process:

- 5 months
- \$500K design fees
- True understanding of budget



Transparency

Conditions of Satisfaction

CONDITIONS OF SATISFACTION

(developed by design team in IPD worksession on February 20, 2013, updated April 2, 2013)

PHASE I — CONCEPTUAL DESIGN


- An aesthetically beautiful building design that inspires donors
- Performance metrics that inspire the project team and donors
- Flexible fund-raising opportunities developed collaboratively
 by the team
- Team integration and alignment on performance metrics
- The right team members attend the right meetings at the right time
- A high-performing lean team that fulfills commitments on time
- A team that has fun, and throughout the project, remains friendly and respectful

PHASE II — FINAL DESIGN / CONSTRUCTION


- A beautiful, high-performance building that is embraced by and enlivens Basalt & RMI
- A building that is replicable in the marketplace
- Town-of-Basait approval of a building design that works for RMI
- RMI site unencumbered by 100-year floodplain.
- Fair profit for all team members
- Formal project-team agreement to "integrated project delivery" at Phase 2 launch
- Zero "change orders" (OO's) and no unnecessary "requests for information" (RFI's)



Key Performance Indicators



NorthShore Niles MOB - Project Dashboard



Risk Assessment and Tracking

	orthShore			Norti	hShore Ni	les MOB - RISK/ OPPORTUNITY TRACKER		
Item N	Risk/Opportunity Description	Assessed Risk	Accepted -	Rejected -	BIC ,	Actions Required for Approval	Pros	
1.01	Delay start of project until spring to avoid winter conditions			(20,000)	REJECTED	Rejected - Provides little savings and unacceptable push in schedule		
3.01	Eliminate Roof Deck Concrete			(78,000)	REJECTED	Rejected - Would cause too much future cost should the 2nd floor go forward. The savings would also likely be less due to additional structural		
3.01	Concrete additive in lieu of surface applied moisture mitigation for flooring			0	REJECTED	Researched Ardus concrete additive. Works out to \$5.50/sf in additional cost. Not competitive with moisture mitigation. Recommend rejecting.		
4.01	A - Provide alternative brick - Glenn Gary	(3,050)			APPROVED	John review with Northshore. John to get pictures of sample projects.		
4.01	B - Provide alternative brick - General Shale	(6,510)			REJECTED	projects.		
4.01	C - Provide utility versus modular bricks - IL Brick	(34,000)			REJECTED	John review with Northshore. Mike S. to send John pictures of sample projects. Brick samples to arrive Tuesday at IFS main office.		
4.02	Provide cast stone or precast in lieu of limestone brick and remove limstone between windows.				REJECTED	Mike and Jeff to work together to define scope and price of reduction in the amount of limestone in the project		
5.01	Substitute composite roof deck with standard roof deck 3" N20 ga.			(\$4,000)	REJECTED	Rejected - 2nd Story is required. Check hangers requirements, envelope	Cost savings.	N/A if keeping 2
5.02	Substitute composite roof deck with standard form deck.			(\$4,000)	REJECTED	Rejected - 2nd Story is required. Check hangers requirements, envelope	Cost savings.	N/A if keeping 2
5.03	Eliminate 6" 18-gauge metal studs and in-wall R-19 batt insulation with kraft facing/vapor barrier, replace with 3-5/8" 18-gauge metal studs at perimeter wall conditions of building.		(2,000)		APPROVED	3.5" polyiso rigid insulation in lieu batten insulation with 3 - 5/8" studs.	Keeping the insulation and vapor barrier on the exterior of the perimeter walls and not within the stud cavities will give a more efficient envelope and allow for future renovation to occur within the stud walls, such as moving walls and outlets, to occur without	No issues.

Coaching for Owner's




Coaching for Owner's




- 1. Performance Improvement
- 2. Objective Feedback
- 3. Accountability
- 4. Knowledge Gain
- 5. Positive Reinforcement
- 6. Sounding Board

Integrated Form of Agreement




TRI-PARTY AGREEMENT



POLY-PARTY AGREEMENT

Integrated Form of Agreement





Other Resources for Owner's















In the spirit of continuous improvement, we would like to remind you to complete this session's survey! We look forward to receiving your feedback.



Contact Us

James Pease

UCSF Health

james.pease@ucsf.edu



John Zachara

Integrated Facilities Solutions, Inc.

jzachara@ifspm.com







