

Developing Cost Awareness in Preconstruction and Design Management



Health precautions to keep everyone as safe as possible at Congress:

- Wear masks at all times in indoor events.
- Complete your daily health screening on your phone and bring it with you when you enter the center each day.
- Practice social distancing to the extent possible.
 Seating at plenary sessions is structured to help with this.
- If you feel ill at any time, please leave the conference and return to your room/consult a physician as necessary.
- Ultimately, our collective health and safety at Congress is up to all of us. Thanks for your support!





Active Estimating and Preconstruction Management

Advanced Studies and Professional Concentration Program



Problem Statement

The roles of a pre-construction team are fundamentally shifted in the TVD environment

- Actively predict cost using incomplete information
- Provide rapid cost feedback to design
- Collaborate with the design team to steer cost to targets
- Must balance project dynamics

Learning Objectives

Understand	Implement	Lead
 full-cycle approach in estimating 	 behavioral estimating practices that increase activeness and predictability 	 lead changes in continuous estimate implementation
 conduct highly collaborative interactions and shared vision with the owner and design team 	 integrating new technology and innovations 	

A Story

Gypsum Board Assemblies Cost Model


\$/SF Aggregate Unit Cost based on:

- Benchmark project
- Wall and ceiling densities


How does new hospital compare to historical data and assumptions?



Risky Business



Production and Analysis



QA Schedule - Interior Partition Types - CE						
Туре	Type Mark	Assembly Description	Width	Structure Thickness	Area	Length
LEVEL 0B1			V	3.		
Type 00TL	00TL		4"		18874.12 SF	1228' - 10 17/32"
Type A4 - Single Layer GWB - NR - STC-35 - 4" Stud	A4	Partitions - Drywall w/ Metal Stud	5 1/4"	4"	19421.96 SF	109' - 2"
Type A6R - Single Layer GWB - 1HR - STC-35 - 6" Stud	A6R	Partitions - Drywall w/ Metal Stud	7 1/4"	6"	11891.1 SF	784' - 10 3/16"

Findings and Results

	Floor Level/	
_	Department	Totals
Wall Footage Extractions		
Calibration 1.6 % Increase		
Assumption %		
Assumption Wall Footage		
Total Model w Assumptions		
Wall Footage OST		
Assumed/Missing OST		
Total OST Footage		
Percentage Increase		
Hard Lids		
Sterile Clinical		
Floor Plate OST		
Floor Plate Revit		
Wall Density OST		
Wall Density Revit		
Ceiling Density OST		
Ceiling Density Revit		

	Benchmar	% Change 9.85%	Value \$5.5 M
Wall Density_ Ceiling Density	0.132 0.143	-25.87%	- \$1.0 M
	0.110	RISK TO PROJECT	\$4.5 M

Active Estimating

Passive Objective



Status of Design

Active Subjective

Inert State

Quantification Critical Thinking Quantification **Active State**

TIME

Leveraging Technology for Continuous Estimating





Continuous Estimating—The Challenges

Regularly update the estimate


and track variances from the last update


while design is progressing.






Subjective/Objective Tracking





Leverage Technology

- All design model hosted on the cloud
- Allow collaboration between design teams (A, S, MEP, Civil...) and Trade Partners
- Sharing incomplete information
- Continuously track changes



Leverage Technology



The Trade Contractor Role in TVD




Trade Contractor—Conceptual Estimating

- Estimating Ahead of Design Documents
- High Aggregate \$/SF
 Unit Cost—Historical Data
- Making adjustments
 - Code Cycle Updates
 - Scope of Work Differences
 - Site conditions

,					ancisco
Project Metrics					
Actual Manhours/SF incl SUPV			570,319		0.57
Total Branch Raceway LF/SF (MC/EMT)			1,277,337		1.64
Branch Conduit	ı		730,087		0.94
MC Cable	ı		547,250		0.70
Feeder Raceway/SF	ı		89,262		0.11
Qty of Light Fixtures	Ì		14,378		0.02
Materials	Ì		-		
Lighting Fixtures	Ì	\$	7,270,667		9.35
Lighting Control	Ì	\$	1,524,718		1.96
Switchgear	ı	\$	8,831,580		11.35
Generators	Ì	\$	6,482,674		8.33
Temp Power		\$	1,038,560		1.33
FOMs		\$	286,153		0.37
Commodity Materials (cond,wire,misc)		\$	7,664,450		9.85
Total Materials (Code 300)		\$	33,098,802		42.54
Tel Data Fire Alarm Lightning Protection Nurse Call/Infant/Access/CCTV Rigging Core Drilling Misc Subcontractors Totals	/AOR		\$ 13,476,594 \$ 2,973,670 \$ 104,525 \$ 10,527,366 \$ 39,220 \$ 232,528 \$ 92,042 \$ 27,837,651	17.32 3.82 0.13 13.53 0.05 0.30 0.12 35.78	

Conceptual Estimating & Design

- Mark-Ups of Typical Rooms
- Inform Design Team
 What is Included in
 High-Aggregate \$/SF
 Estimate
- Provide Initial
 Framework for Design



Informing Target Value Design

New Hospital Switchgear KPI

Note: Positive value = savings & negative = overage

Equipment Type	Benchmark SLD Take-Off	Benchmark KPI/SF	New Hospital Base KPI	New Hospital SLD Take-Off	Delta	Notes
FS SWB w/ 12KV SW,						
				9		
				30		
12KV Switch				9		
				30		
				9		
480v/208v						
				90		
480v Distribution						
				48		
120 Distribution						Overage may be offset by reduction in feeder lengths. Further
Board	11	0.0000141388	12	58	(46)	evaluation required.
						Overage may be offset by reduction in feeder lengths. Further
				108		
120/208v Panelboard	324	0.0004164524	354	264	90	Possible savings. Awaiting final switchgear quote.



Key Takeaways

Active and full-cycle approaches in estimating are needed to support TVD.

Behavioral changes are critical in implementing Active Estimating.

 BIM, data analytics, and visuals improve estimating workflow and enable incomplete information sharing and rapid cost feedbacks.





In the spirit of continuous improvement, we would like to remind you to complete this session's survey! We look forward to receiving your feedback.



Contact Us

Paul Martin

UC Davis psmmartin@ucdavis.edu

Joseph Leoncavallo

Rosendin Electric jleoncavallo@rosendin.com

Hung Nguyen

Herrero Builders hnguyen@herrero.com

Jennifer Taylor

HDR
Jennifer.taylor@hdrinc.com



Thank you for attending this presentation. Enjoy the rest of the 23rd Annual LCI Congress!

