

25<sup>TH</sup> ANNUAL



25<sup>TH</sup> LCI CONGRESS  
OCTOBER 24-27, 2023

# Leveraging Lean and VDC to Eliminate Deferred Submittals

Jessica Mistretta, Tami Chen, Neil Moreland,  
Arne Knutsen, John Medvec

**25 YEARS OF LEARNING: SUPERCHARGE YOUR LEAN JOURNEY IN THE MOTOR CITY**

October 25, 2023



# Presenters



**Jessica Mistretta**

*Oregon Health & Science University*

**Tami Chen**

*NBBJ*

**Arne Knutsen**

*Southland Industries*

**Neil Moreland**

*Cherry City Electric*

**John Medvec**

*Skanska*



# Problem Statement

The project team established a goal of being fully coordinated prior to submitting a permit application to the Authority Having Jurisdiction (AHJ).

How do we accomplish the goal and know we are fully coordinated?

- Utilize VDC to model to a higher Level of Detail (LOD > 300)
- Trade partners will develop BIM for the Engineer of Record (EoR)
- Eliminate traditional Deferred Submittals (DFS) by having Delegated Design elements completed and submitted with the Building Permit Application.

# Project Goals & Desired Benefits

Fully coordinated construction model prior to submitting a permit application. No deferred submittals to keep on time with the construction schedule.

## Owner

- Better overall coordination
- Improved Timeline

## Design Team

- Fully coordinated model with the architectural design & limit changes during construction


## Contractor

- Reduce RFI's
- 350 Requests for Information (RFIs), at \$150 million complete
- Capture all scope up front

## Sub-Contractors/ Trade Partners


- More efficient workflow
- Submittals complete prior to construction
- Accurate workforce planning

# Example of Fully Coordinated Model vs. Traditional Model



## Typical Model

- Permit submission is generally coordinated but not ready-to-build.





## Fully Coordinated Model

- Requires submittal approval in order to model to LOD >300 and be constructable.
- Submittals are approved prior to completion of Construction Documents (CDs).
- Trade Partners remain flexible to design changes as CDs are completed.
- AHJ reviewed traditionally deferred submittals with the permit plan review




# Team Structure





# Project Introduction





# General Strategies



- Functional Teams
- Big Room & Pull Plans
- Colocation (In-Person & Virtual)
- Establish Conditions of Satisfaction
- Agree upon definition of Fully Coordinated
- Roles & Responsibilities between design & trades
- Trades engaged in modeling early





# Team Culture



- Flexibility
- Accountability
- Representation
- Equal Voices
- Humility
- “Ask the dumb questions”
- StrengthsFinder
- Functional Team "Award of the Week"




# Challenges






# Delegated Design Process



- Early funding for long lead and PO required submittals ex. Generators, Chillers etc.
- Staffing and process of vendors and NSS designers to keep up with the fluid model and design-ex. BB sessions for submittals
- General submittals vs shop drawing factory submittals-Ex. Square D, Caterpillar
- Owner and project approval of submittals before permit/City submission.
- Design far enough ahead for detailed submittals
- Spec differences and as-building specs to submittals.
- Approved submittals and process during design

# Delegated Design Process




## Outcome

- Ability to adjust design with submittal information rather than a cost and schedule impact with submittal design deviations
- Ability to incorporate more of trade partner influence in design for best practices and install methods.
- Ability have further detail for installation rather than design as it is being built.



# Project Start/Stop/Restart

## Lessons Learned



## Challenges

- Project shutdown 2020 & 2021, transition from in-person to virtual
- Program Change
- Permits for Package 1 and 2 and design review complete for structure and envelope
- Allowed us to bring on additional trade partners
- Pull planning to validate project schedule before restarting

# Project Start/Stop/Restart



## Lessons Learned

- Shift in access/conversations from Owners to Trades/Design
- Shift to being over scheduled
- Delay in decision making
  - Narrowed voices from users
- Lost culture





# Pull Planning

## Challenges

- Disorganized start
- Some key design team members did not have pull planning experience
- Trade partners had experience in pull planning but not leading a design pull
- Too many internal activities on the board
- Unclear links between predecessors and successors
- Confusion

## Response

Created separate functional team pull plans to feed into the overall.

- Keep tasks with predecessors and successors that were internal to the FT's off of the main pull plan
- Link tasks that were relative to overall pull plan

## Lessons Learned

- Last Planner Facilitator from the start
- Track variances and PPC in a log and review weekly

# Successes



# How did we do?

<b>Package 1 (Site Clearing, Demolition, Shoring, Excavation)</b>	<b>Deferred</b>	<b>Submitted</b>
Permanent Shoring		<b>X</b>
Temporary Shoring		<b>X</b>
Occupant Safety Plan		<b>X</b>
<b>Package 2 (Deep Foundations, Footings, Backfill, U.G. Utilities)</b>		
Fire Water Storage Tank, UG Fire Suppression Piping		<b>X</b>
Occupant Safety Plan		<b>X</b>
<b>Package 3 (Superstructure, Exterior Enclosure)</b>		
Curtainwall System		<b>X</b>
Steel Stairs		<b>X</b>
Spray Fire Resistant Material (SFRM)	<b>X</b>	
Occupant Safety Plan		<b>X</b>




# How did we do?

<b>Package 4 (Interior Buildout)</b>	<b>Deferred</b>	<b>Submitted</b>
Non-Structural Seismic Anchorage & Bracing of MEP Systems		<b>X</b>
Fire Suppression		<b>X</b>
Interior Framing		<b>X</b>
Guardrails		<b>X</b>
Occupant Safety Plan		<b>X</b>
Thermal Calculations		<b>X</b>
Fire Alarm and 2 way communication plans	<b>X</b>	<b>X</b>

## 93.75% Success Rate

# Positive Outcomes



- Early purchase orders to procure equipment in design phase
- Cost certainty in-lieu-of allowances
- Detailing is done by the time of permit submission vs. during installation
- Prefabrication modeled and coordinated in design – multi-trade rack and headwalls
- Coordination of Mechanical, Electrical, Plumbing, Pneumatic Tube, Fire Suppression anchorage and seismic bracing prior to permit submission
- Interior framing, bracing and blocking prior to permit submission



# Key Tools / Processes







# Tools





IPA - Virtual Pull Plan							
File Automation Forms Connections Dynamic View							
Card View Filter Off All Levels View by FUNCTIONAL TEAM							
Uncategorized (50)	Structural (35)	Interior (160)	Technology (77)	Electrical (111)	Mechanical (69)	Vert. Transp. (19)	Envelope (76)
<div>IPA PROGRAMMING</div> <div>274</div> <div>144d</div> <div>11/01/21</div> <div>05/27/22</div> <div>100%</div> <div>Complete</div>	<div>STRUCTURAL PP3 HEADER ROW</div> <div>Design/detail site walls, reconfigure for POE vault r...</div> <div>031</div> <div>PP3</div> <div>30d</div> <div>05/13/22</div> <div>06/24/22</div> <div>100%</div> <div>Complete</div>	<div>INTERIOR PP1 HEADER ROW</div> <div>Select Patient Lift Option - for serve bath room</div> <div>197</div> <div>PP4</div> <div>14d</div> <div>04/11/22</div> <div>04/28/22</div> <div>100%</div> <div>Complete</div>	<div>TECHNOLOGY PP1 HEADER ROW</div> <div>Review DD Low Voltage Proposals</div> <div>159</div> <div>PP4</div> <div>30d</div> <div>06/30/22</div> <div>08/11/22</div> <div>100%</div> <div>Complete</div>	<div>ELECTRICAL PP4 HEADER ROW</div> <div>L2 G ELEC. RM CHASE FINALIZED</div> <div>053</div> <div>PP4</div> <div>10d</div> <div>03/28/20</div> <div>03/16/22</div> <div>100%</div> <div>Complete</div>	<div>01 PACKAGE 1</div> <div>FUEL TANK LOCATION DEFINED</div> <div>055</div> <div>PP1</div> <div>1d</div> <div>03/23/20</div> <div>03/23/20</div> <div>100%</div> <div>Complete</div>	<div>VERTICAL PP3 HEADER ROW</div> <div>Elevator Shop Drawings Elevators 1-4 &amp; 8-9</div> <div>209</div> <div>PP3</div> <div>21d</div> <div>04/27/20</div> <div>04/25/20</div> <div>100%</div> <div>Complete</div>	<div>ENVELOPE PP3 HEADER</div> <div>INTEGRATE BLDG MOUNTED LIGHTING</div> <div>051</div> <div>PP3</div> <div>1d</div> <div>04/09/22</div> <div>04/09/22</div> <div>100%</div> <div>Complete</div>
<div>IPA PROGRAMMING</div> <div>KICK-OFF AND PROCESS PLANNING</div> <div>275</div> <div>5d</div> <div>11/01/21</div> <div>11/03/21</div> <div>100%</div> <div>Complete</div>	<div>STRUCTURAL PP3 HEADER ROW</div> <div>PRIMARY STRUCTURAL DESIGNED FOR STAIR LOA...</div> <div>063</div> <div>PP3</div> <div>20d</div> <div>03/23/20</div> <div>04/17/20</div> <div>100%</div> <div>Complete</div>	<div>INTERIOR PP3 HEADER ROW</div> <div>Confirm extent of Level 3 Imaging depressions and e...</div> <div>535</div> <div>PP3</div> <div>0</div> <div>04/19/22</div> <div>04/19/22</div> <div>100%</div> <div>Complete</div>	<div>TECHNOLOGY PP3 HEADER ROW</div> <div>IDENTIFY BEAM PENETRATIONS TO BIM M...</div> <div>185</div> <div>PP4</div> <div>30d</div> <div>04/01/20</div> <div>05/12/20</div> <div>100%</div> <div>Complete</div>	<div>ELECTRICAL PP3 HEADER ROW</div> <div>BLDG MOUNTED EXTERIOR LIGHTING HAND-OFF TO E...</div> <div>089</div> <div>PP4</div> <div>20d</div> <div>03/28/20</div> <div>04/22/20</div> <div>100%</div> <div>Complete</div>	<div>02 PACKAGE 2</div> <div>FUEL TANK MEP SITE COORD. WORK SESSION</div> <div>107</div> <div>PP2</div> <div>0</div> <div>04/15/20</div> <div>04/15/20</div> <div>100%</div> <div>Complete</div>	<div>VERTICAL PP3 HEADER ROW</div> <div>Elevator 7 Type Confirmati...</div> <div>210</div> <div>PP3</div> <div>15d</div> <div>04/27/20</div> <div>05/15/20</div> <div>100%</div> <div>Complete</div>	<div>02 PACKAGE 2</div> <div>GROUND LEVEL ENCLOSURE DEPTH / DET.</div> <div>047</div> <div>PP2</div> <div>11d</div> <div>03/18/20</div> <div>03/30/20</div> <div>100%</div> <div>Complete</div>
<div>IPA PROGRAMMING</div> <div>DESIGN WORKSHOPS DE-RAD ONC</div> <div>276</div> <div>30.125d</div> <div>11/29/21</div> <div>01/12/22</div> <div>100%</div> <div>Complete</div>	<div>03 PACKAGE 02</div> <div>PKG 02 Review Floor Penetrations</div> <div>118</div> <div>PP3</div> <div>5d</div> <div>04/20/20</div> <div>04/24/20</div> <div>100%</div> <div>Complete</div>	<div>INTERIOR PP3 HEADER ROW</div> <div>REVISE PP3 DR SCHEDULE &amp; UPLOAD TO JOE CROSS</div> <div>196</div> <div>PP3</div> <div>14d</div> <div>04/20/22</div> <div>05/23/22</div> <div>100%</div> <div>Complete</div>	<div>TECHNOLOGY PP4 HEADER ROW</div> <div>Populating the 5th floor with Communications Outlets</div> <div>157</div> <div>PP4</div> <div>100d</div> <div>07/19/22</div> <div>12/06/22</div> <div>100%</div> <div>Complete</div>	<div>ELECTRICAL PP3 HEADER ROW</div> <div>VIBRATION CRITERIA FINALIZED</div> <div>028</div> <div>PP3</div> <div>1d</div> <div>04/16/20</div> <div>04/16/20</div> <div>100%</div> <div>Complete</div>	<div>MECHANICAL PP3 HEADER ROW</div> <div>Mechanical Systems Size RCD</div> <div>484</div> <div>PP3</div> <div>11d</div> <div>03/17/22</div> <div>03/13/22</div> <div>100%</div> <div>Complete</div>	<div>VERTICAL PP3 HEADER ROW</div> <div>Elevator 7 Basis of Design Confirmed</div> <div>211</div> <div>PP3</div> <div>140d</div> <div>02/18/22</div> <div>04/07/22</div> <div>100%</div> <div>Complete</div>	<div>ENVELOPE PP3 HEADER</div> <div>WALKWAY DESIGN CRITERIA</div> <div>087</div> <div>PP3</div> <div>20d</div> <div>03/25/20</div> <div>04/21/20</div> <div>100%</div> <div>Complete</div>
<div>04EP IPA Pull Plan</div> <div>03 PACKAGE 3</div> <div>024</div> <div>35d</div> <div>02/20/20</div> <div>11/20/23</div> <div>99%</div> <div>Complete</div>	<div>STRUCTURAL PP3 HEADER ROW</div> <div>Loading dock framing design, docks detailed</div> <div>032</div> <div>PP3</div> <div>45d</div> <div>04/22/22</div> <div>06/24/22</div> <div>100%</div> <div>Complete</div>	<div>INTERIOR PP1 HEADER ROW</div> <div>WALL TYPES DEFINED DO</div> <div>043</div> <div>PP4</div> <div>90d</div> <div>05/09/22</div> <div>08/10/22</div> <div>100%</div> <div>Complete</div>	<div>TECHNOLOGY PP4 HEADER ROW</div> <div>Division 27 Technology Specifications</div> <div>158</div> <div>PP4</div> <div>25d</div> <div>06/04/22</div> <div>06/06/22</div> <div>100%</div> <div>Complete</div>	<div>ELECTRICAL PP4 HEADER ROW</div> <div>BLDG INTERIOR LIGHTING HAND-OFF TO SEPT</div> <div>070</div> <div>PP4</div> <div>0</div> <div>04/22/20</div> <div>04/22/20</div> <div>100%</div> <div>Complete</div>	<div>MECHANICAL PP3 HEADER ROW</div> <div>L11 Model Plumbing &amp; Wet Mechanical</div> <div>542</div> <div>PP3</div> <div>20d</div> <div>01/30/23</div> <div>02/27/23</div> <div>52%</div> <div>In Progress</div>	<div>VERTICAL PP3 HEADER ROW</div> <div>Elevator engineering and systems fully coordinated ...</div> <div>478</div> <div>PP3</div> <div>160d</div> <div>04/01/22</div> <div>11/16/22</div> <div>100%</div> <div>Complete</div>	<div>ENVELOPE PP3 HEADER</div> <div>EXTERIOR SHAFT WALLS LOCKED</div> <div>040</div> <div>PP3</div> <div>38d</div> <div>02/18/22</div> <div>04/13/22</div> <div>100%</div> <div>Complete</div>
<div>04EP IPA Pull Plan</div> <div>04 PACKAGE 4</div> <div>025</div> <div>10.22d</div> <div>04/10/20</div> <div>04/10/20</div> <div>100%</div> <div>Complete</div>	<div>STRUCTURAL PP3 HEADER ROW</div> <div>All exterior site</div> <div>031</div> <div>PP3</div> <div>100d</div> <div>04/10/20</div> <div>04/10/20</div> <div>100%</div> <div>Complete</div>	<div>INTERIOR PP1 HEADER ROW</div> <div>SECURITY CHECK POINTS DESIGN</div> <div>031</div> <div>PP3</div> <div>100d</div> <div>04/10/20</div> <div>04/10/20</div> <div>100%</div> <div>Complete</div>	<div>TECHNOLOGY PP4 HEADER ROW</div> <div>Provide a Close Source</div> <div>031</div> <div>PP3</div> <div>100d</div> <div>04/10/20</div> <div>04/10/20</div> <div>100%</div> <div>Complete</div>	<div>ELECTRICAL PP4 HEADER ROW</div> <div>IDENTIFY BEAM PENETRATIONS TO BIM M...</div> <div>031</div> <div>PP3</div> <div>100d</div> <div>04/10/20</div> <div>04/10/20</div> <div>100%</div> <div>Complete</div>	<div>MECHANICAL PP3 HEADER ROW</div> <div>L11 Identify Supplemental Steel Needs - Coordinate ...</div> <div>031</div> <div>PP3</div> <div>100d</div> <div>04/10/20</div> <div>04/10/20</div> <div>100%</div> <div>Complete</div>	<div>VERTICAL PP3 HEADER ROW</div> <div>031</div> <div>PP3</div> <div>100d</div> <div>04/10/20</div> <div>04/10/20</div> <div>100%</div> <div>Complete</div>	<div>ENVELOPE PP3 HEADER</div> <div>031</div> <div>PP3</div> <div>100d</div> <div>04/10/20</div> <div>04/10/20</div> <div>100%</div> <div>Complete</div>

# Tools





# Tools





# Lessons Learned



# How can you apply this tomorrow?

On-board vendors early	Identify your delegated design submittals
Define ‘DONE” Yes, I’m done?	On-board Authorities Having Jurisdiction
Actionable conversations	
Plan submittal review into design schedule	
Clear goals memorialized	
The whole team needs to be onboard with clear expectations of the goals	
Hire Last Planner Facilitator at the start	





# Would we do this again?

*"Fully coordinated? – YES!..." - Jessica*

*"....everyone is an expert & removes bottlenecks of information" - Tami*

*"More efficient field execution" - Arne*

*"The extra work up front opens more opportunities." - Neil*

*"It's a challenge" - John M*







25<sup>TH</sup> LCI CONGRESS  
OCTOBER 24-27, 2023



**In the spirit of continuous improvement, we would like to remind you to complete this session's survey! We look forward to receiving your feedback.**



# Contact Us



**Jessica  
Mistretta**

**Mistreja@  
ohsu.edu**



**Tami  
Chen**

**TChen@  
nbbj.com**



**Neil  
Moreland**

**Nmoreland@  
cherrycityelectric.  
com**



**Arne  
Knutsen**

**AKnutsen@  
southlandind.com**



**John  
Medvec**

**John.medvec@  
skanska.com**

