



Lean Construction Institute
Immersive Education Program

Target Value Delivery Module 3: Organizing for Flow & Efficiency

Julie Glassmeyer

Glassmeyer Construction Consulting
& Coaching, LLC

Michelle Whiteside
Brasfield & Gorrie

October 22, 2024







LCI Course:
Target Value Delivery Module 3:
Organizing for Flow & Efficiency
4 CEU

Sign the sign-in sheet for credit



**Approved
Continuing
Education**


Download the Congress event app



Download the Congress event app



- Plan your schedule in your personal agenda
- Browse all available sessions
- Read speaker profiles
- Navigate to your session on the venue map

Scan this QR Code to
download the app



Rate Session In Event App

Plan to evaluate
each session you
attend in the
event mobile app!



TVD Modules

Module 1: Learning the Fundamentals

- Gain insight into how implementing TVD approaches improves project outcomes through an overview of the phases and key components of TVD.

Module 2: Setting the Stage for Success

- Discover how creating early alignment and understanding of the owner's Business Case, Value Statements and Conditions of Satisfaction will lead to successful outcomes and how these foundations become the anchor for future decisions.

Module 3: Organizing for Flow and Efficiency

- Discover how teams can be challenged with maintaining effective processes and engagement through creating a cross-functional work cluster organization as a highly effective means of driving innovation and productivity through concurrent work.

Module 4: Modeling for Predictable Outcomes

- Experience a framework for predictive cost modeling, target setting and rapid innovation capture in collaborative TVD environments.

Learning Objectives



Discover how to effectively organize and manage teams in cross functional, interconnected work clusters and how cluster groups engage with cost model and Last Planner System in Design.



Discover the importance of key leadership roles and responsibilities that are foundational to the successful implementation of Target Value Delivery, information management, and decision making.




Identify what are the characteristics of effective facilitation and Lean practices at a project and work cluster level for Target Value Delivery to support information flow.



Understand information and decision-making workflow across clusters and from cluster groups to decision making authorities within team and how to manage owner prerogative in the context of consensus driven decision making.

Lean Journey to Mastery

How will you reach the next level on your journey?



Project Elements

Lean teams organize in a structure that leads to improved coordination, outcomes and shared leadership.



Lean can be implemented regardless of commercial terms: Design-Bid-Build, Design-Build or Integrated Project Delivery. The degree of implementation varies with the terms.

A Lean Operating System is a organized implementation of Lean Principles and Tools combined to allow a team to operate in unison to create flow.



Six Tenets of Lean Construction

- 1 Respect for people
- 2 Optimize the Whole
- 3 Generate Value
- 4 Eliminate Waste
- 5 Focus on Flow
- 6 Continuous Improvement



Target Value Delivery

8:00 AM – Class Begins

9:45 AM – Break 15 minutes

12:00 PM – Class Adjourns



Rules of Engagement



This is a safe zone



Use E.L.M.O.



Everyone has equal status



Silence phones



Speak up and share your ideas



Be focused and engaged



Actively listen to others



Stay on time





One conversation at a time



Have fun!

References





Introduction / Discussion

Introduction: Who you are, What you do & What you hope to get from the day.

Discuss challenges associated with team organization and information flow?

15 MINUTES

Participants' CoS

What do you want to gain from this workshop?


TVD Definition

A disciplined management practice to be used *throughout* the project to ensure:

- The facility meets the operational and performance *needs and values* of the users.
- The project is delivered within the *allowable budget, schedule, and intended scope*.
- That *innovation* is promoted throughout the process to *increase value* and eliminate waste.

Target Value Delivery (TVD)

Target Value Delivery *encompasses* Target Value Design **AND** Target Value Production (Construction).




Application

Target Value Delivery is to be applied **holistically** to obtain maximum value.


Regardless of the project delivery framework, the owner, designers, builders, and key trades must be **fully engaged** from the onset.

It generates a **creative tension** between driving up quality YET driving cost down.




Traditional vs. Target Value Delivery

The goal of TVD is to minimize the waste produced by the design, estimate and redesign cycle(s) of the traditional value engineering approach.




TVD Phases Overview


- This graphic depicts the relationship between the TVD Phases and the Targets.
- Targets may include cost, time and quality as defined by the Value Definition.



Target Value Delivery (TVD) Overview



Target Value Delivery (TVD) Overview



Team Structure Formation



Team Kick-Off Workshop

- Why: Create necessary alignment among all team members
- Who:
 - Project leadership
 - Core team
 - End user stakeholders as necessary
 - Day to day team members / design implementation team
- What:
 - Team building and goal alignment
 - Define team structure, roles and responsibilities, decision workflow, etc.
 - Design planning
 - Learning

Kick-Off Meeting Examples



Oldcastle Project Flagship – Kickoff Agenda

Date | Location

Day 1 – Team Dynamics

8:00am	Breakfast
8:30am	Commencement Open Meeting, Purpose Moment, Review Agenda & Project Overview
9:00am	Introductions Team Introductions & Ice Breaker
10:00am	Break
10:30am	Measures of Success Project Goals & Measures of Success
11:00am	Team Organization Team Organization, Roles & Responsibilities
11:30am	Lunch
12:30pm	Team Activity
1:00pm	Collaboration Strategy Team Communication, Meeting Cadence & BIM Execution Plan
2:00pm	Design Assist Trade Partner Strategy
2:30pm	Break
3:00pm	Focus Session Project Specific Focus Session – TBD
4:00pm	Adjourn Plus/Delta & Adjourn
6:00pm	Team Social Location TBD
7:00pm	Dinner



Oldcastle Project Flagship – Kickoff Agenda

Date | Location

Day 2 – Team Workshops

8:00am	Breakfast
8:30am	Commencement Open Meeting, Review Agenda & Ice Breaker
9:00am	Schedule Workshop Major Milestones & Design Decision Planning
12:00pm	Lunch
1:00pm	Budget Workshop Cost Review & Design Alignment
4:00am	Adjourn Plus/Delta & Adjourn

UAB MedWest

Team Kick-Off Day 2

Date: 7/15/2020
Location: BlackJack Farm
Time: 8:00:00 AM
Facilitator: Katie Wells
Time Mgr: Stephen Powell

Start	End	Duration (minutes)	Topic	Leader	Comments / Resources / Homework	Needed Attendees
8:00:00 AM	8:30:00 AM	30	Breakfast / Socialize			
8:30:00 AM	9:00:00 AM	30	Introduction / Agenda Overview / Ice Breaker	Facilitator		Core Team
9:00:00 AM	11:00:00 AM	120	Budget Discussion	Jud	Overall Budget Discussion	Core Team + Nick Harper
11:00:00 AM	11:15:00 AM	15	Break			
11:15:00 AM	12:45:00 PM	90	Component Team Discussion - MEP and Structural / Lunch	Jud / Stephen	Structural System and MEP System Review	Core Team
12:45:00 PM	1:45:00 PM	60	Design Assist Partner Onboarding Discussion	Jud / Stephen	How are we onboarding and what are design-assist partner expectations?	
1:45:00 PM	3:35:00 PM	110	Team Collaboration Strategy (see subtopics below)	See below		
3:35:00 PM	4:05:00 PM	30	Review Agenda for Day 3	Facilitator		Core Team
4:05:00 PM	4:20:00 PM	15	Plus / Delta	Facilitator		Core Team
4:20:00 PM	6:20:00 PM	120	Social Time / Dinner			
		Total	18.33 Hours			

Start	End	Duration (minutes)	Topic	Leader	Comments / Resources / Homework	Needed Attendees
1:45:00 PM	2:05:00 PM	20	Big Room Frequency and Location / Check in Calls	Katie / Stephen		Core Team
2:05:00 PM	2:25:00 PM	20	Method for Cost Control - Tabbed	Jud	Example for Review	Core Team
2:25:00 PM	2:45:00 PM	20	Decision Documentation (A37) - Tabbed	Katie / Stephen	Example for Review	Core Team
2:45:00 PM	3:15:00 PM				Document management, collaboration space.	

UAB MedWest


Team Kick-Off Day 3

Date: 7/16/2020
Location: BJ Farm
Time: 8:00:00 AM
Facilitator: Katie Wells
Time Mgr: Stephen Powell

Start	End	Duration (minutes)	Topic	Leader	Needed Attendees
8:00:00 AM	8:30:00 AM	30	Breakfast / Socialize		
8:30:00 AM	8:50:00 AM	20	Agenda Overview / Ice Breaker	Facilitator	Core Team
8:50:00 AM	10:20:00 AM	90	Pull Planning Validation Package	Facilitator	Core Team
10:20:00 AM	10:35:00 AM	15	Break		
10:35:00 AM	12:05:00 PM	90	Pull Planning Validation Package	Facilitator	Core Team
12:05:00 PM	12:50:00 PM	45	Lunch		Core Team
12:50:00 PM	1:20:00 PM	30	Wrap Up / Next Steps	Facilitator	Core Team
1:20:00 PM	1:40:00 PM	20	Plus / Delta	Facilitator	Core Team
1:40:00 PM	2:40:00 PM	60	Prepare to Report out to ELT	Stephen	Core Team
2:40:00 PM	3:40:00 PM	60	Report Out to ELT	Stephen	Core Team
		Total	7.67 Hours		

Work Cluster Organization – Why?

- Breaks down project complexity for rapid learning and decision making
- Cross-functional knowledge sharing
- Better informed and well-timed decisions (LESS ITERATION)
- Ensure design solutions aren't made in a vacuum



Source. Team of Teams: The New Rules of Engagement for a Complex World, General Stanley McChrystal, 2015



Work Cluster Organization

Executive/Senior Management:

- Not involved in day-to-day of team
- Resolve conflicts

Core Team:

- Day-to-day leaders of the team

Work Clusters:

- Leader
- System oriented
- Cross discipline
- Stakeholder representation
- Form as need

Work Cluster Leader:

- Coordination between work cluster & core team



Work Cluster Organization

- Formed as necessary for project needs
 - Can be formed ad-hoc around a critical decision
 - Depends on size and complexity of the project
- Should be Multi-disciplinary /Cross Functional
- Examples include:
 - Building System (MEP, skin, structure, site)
 - Department type
 - Big Ideas and Innovation


Leadership & Facilitation

- Leadership: visionary, big picture, leads the group to achieve vision
- Facilitator: brings people together to develop a vision then leads them toward achieving it


****A facilitator can be a leader, but a leader is not necessarily a facilitator**



Cluster Examples



Cluster Examples



Cluster Examples




Project E.A.S.T. Updated 10/05/2021										
TV2 CLUSTERS & PIT's										
TV2 Clusters ... teams designing to a target cost										
STRUCTURE	EXTERIOR ENVELOPE	CONVEYING	MECHANICAL, PLUMBING & ELECTRICAL	SITE / CIVIL	INTERIOR FF	TECHNOLOGY	MEDICAL EQUIPMENT	CEP	DEMO	OPERATIONS/ TRANSITION
Matt O'Callaghan	Kerry Bennett	Arch	Wes Richardson	Kelwy Howard	Adam Chahulski	Josh Snyder	John Sion	Justin Swanson	Jason Goltsbein	
Dan Isenogle	Eric Valters	Tommy Milbrot	Bill Payne	Steve Holladay	Eric Valters	Lois Harris	Daniel James	Amanda Melton	Steve Holladay	Eric Valters
Tim Duboski	REC Agent	T.R. Bowers	Joel Snyder	MEP Co Agent	Joel Palmer	Kim Carrison	E.J. McCrea	Chris Palmer	Randall Marshall	Bill Payne
Kerry Bennett	Dan Isenogle	Joel Palmer	Test & Balance	Dan Isenogle	Lee Shore	Kevin Leonard/ Security	Tri Dang	Bill Payne	Lee Shore	Kim Carrison
Kelwy Howard	Greg Luongo	St. Chge	Mark Franklin	Mark Miller	Wes Richardson	Joel Palmer	Randall Marshall	Supply Chain	Mark Miller	Tim Duboski
Stephen Perry	Ryan Griffin		Adam Chahulski	Kerry Bennett	Kerry Bennett	Laura Hild	Lee Shore	Cary Simmons	Adam Chahulski	Matt O'Callaghan
Steve Mann	David Wyatt		Kevin Davis	Matt O'Callaghan	Adam Chahulski	Kerry Bennett	Stephen Perry	David Wyatt	Lauren Edwards	
David Wyatt			Justin Swanson	Elect Sub	Justin Swanson	Molly Livingstone				
Justin Swanson										
Infection Prevention, Emergency Management, Safety, S										
Scope, Systems, etc.										
STRUCTURE	EXTERIOR ENVELOPE	CONVEYING	MECHANICAL, PLUMBING & ELECTRICAL	SITE / CIVIL	INTERIOR FF	TECH				
Structural Systems	Exterior Skin	Elevators	Hvac Equipment	Normal Power	Sitework	Interior Walls				
Foundations	Vestibules, Canopies	P-Tube	Chilled Hot Water/ Steam Piping	Essential Power	Site Utilities	Millwork				
Bridges	Green Roofs	Chutes	CEP Chillers	Lighting - Exterior, Interior, Specialty	Site Permitting	Finishes				
Misc Steel	Roofing		Ductwork	Isolated Power	Traffic Planning	Non-Med Equipment				
Prefab	Waterproofing		Building Automation System	Lighting Protection	Parking Planning	Furniture/ Site Furnishings				
Screen Walls	Fall Protection		Smoke Control	Fire Alarm	Bridges	Signage				
Helipad	Energy Performance		Med Gas, Natural Gas	Raceways & Rough in	Temp Roadways/ Utilities	Artwork				
	Exterior Signage		Dom Water Systems	Duke Power coordination	Retaining Walls	Prefab Strategy				
	Ext lights, antennas, cameras		Storm Sanitary - Building	Prefab Strategy	Fuel Systems	Window Treatments				
			Special Water Systems		Site Signage	Cubicle Curtains				
			Fire Suppression		Parking Equipment	Equipment Finishes				

Weekly Planner for Meetings & Various Sessions

Project EAST

Monday	Tuesday	Wednesday	Thursday	Friday
7:00 AM	7:00 AM	7:00 AM	7:00 AM	7:00 AM
8:00 AM	8:00 AM	8:00 AM	8:00 AM	8:00 AM
9:00 AM	9:00 AM	9:00 AM	9:00 AM	9:00 AM
10:00 AM	10:00 AM	10:00 AM	10:00 AM	10:00 AM
11:00 AM	11:00 AM	11:00 AM	11:00 AM	11:00 AM
12:00 PM	12:00 PM	12:00 PM	12:00 PM	12:00 PM
1:00 PM	1:00 PM	1:00 PM	1:00 PM	1:00 PM
2:00 PM	2:00 PM	2:00 PM	2:00 PM	2:00 PM
3:00 PM	3:00 PM	3:00 PM	3:00 PM	3:00 PM
4:00 PM	4:00 PM	4:00 PM	4:00 PM	4:00 PM
5:00 PM	5:00 PM	5:00 PM	5:00 PM	5:00 PM
6:00 PM	6:00 PM	6:00 PM	6:00 PM	6:00 PM
Team Check-in				
Tech Wkly Check-in				
Enabling Work Planning				
Interiors Cluster				
Enabling Work Planning				
MEP Cluster				
Structure Cluster				
Demo Cluster				
LUNCH				
CEP Cluster				
Site/ Civil Cluster				
Med Equip Cluster				
Decision Council				
IT Furniture Load-in				
Final Cleaning/ An Testing				
Building Keying/ Badging				

Roles & Responsibilities



Roles / Responsibilities

Executive Team Responsibilities

Purpose & Responsibilities
The Executive Team is to monitor overall progress and health of the project, advise project leaders and to act decisively when called upon for decisions or course correction. The Executive Team meets every two weeks or on an as-needed basis. The frequent cadence of this meeting underscores the need for timely responsiveness from the Executive Team in order to ensure project progress.
<ul style="list-style-type: none"> Discuss major decisions with Raytheon Monitor Project Design Progress Monitor Budget vs Cost Monitor Resources needed on the Project Monitor Issues and Risks that Arise

Core Team Responsibilities

Purpose & Responsibilities
Decision Approval / Request Executive Team for Presentation to Raytheon
Monitor Cluster Teams Health and Performance
Resource Management for Overall Team
Adjust Cluster Team Makeup if Needed
Provide Reports / Information to Executive Team
Maintain Master Schedule

Cluster Team Responsibilities

Purpose & Responsibilities
Align Design with Raytheon Expectations
A3 Development / Recommendations to Core Team
Report Progress (Major Decisions and Major Questions) to Core Team
Action Item Management
Maximize value within budget
Activity planning to advance design and meet schedule

What do Cluster Teams Do?

Cluster Groups:

- Develop work based on priorities created with core team
- Analysis and research for presenting decision information
- Set design priorities based on decisions
- Use collaboration tools to provide access to whole team
- Use cost model in each cluster group
- Make sure right balance of team members across groups

Cluster Group Report Outs:

1. Present design set analysis and make recommendations to Core Team
2. What have you been working on?
3. What work will occur over the next work cycle?
4. Risks & Opportunities
5. What upcoming decisions need to be made?
6. Are you on track with your pull plan commitments?

Cluster Member/Leader Responsibilities



- Role Model / Motivate
- Use pull planning to organize work of cluster
- Ensure that cluster's commitments are being met
- Verify cluster member constraints are being removed
- Verify that cluster topics make their way on to agenda
- Represent the cluster in integrated team meetings
- Organize daily cluster check-in structure as appropriate
- Assist with On-Boarding process
- Foster A3 process in decision making
- Foster lean learning and principles



- Make reliable commitments
- Manage commitments to completion
- Make cluster leader aware of any and all constraints
- Actively participate in pull planning
- Actively participate in development of A3's
- Fill in for cluster leader as needed
- Actively pursue lean principles and learning

Project Club House

- LCI has decided to partner with a national non-profit to build a clubhouse that will be donated to a local elementary school.
- We have committed to building (1) Play/Learn Clubhouse this year utilizing lean principles with our LCI members.
- They have identified an elementary school (Pre-k thru 2nd grade, kids aged 4-8 years old) in an underserved community as the recipient of the clubhouse.
- LCI has raised \$55,000.00 to go towards the clubhouse
- The LCI would like to cover the material and labor cost of building the clubhouse and be able to completely furnish it. It would be nice to provide playsets such as a kitchen playset, etc. if savings allow

36



Cluster Group Formation

Cluster Assignment Per Table - Develop:

- Cluster Organization / Leadership / Facilitation
- Cluster Priorities / Purpose
 - What are the 1st 2-3 things we should focus on?
- Develop Cluster Meeting Agenda

20 MINUTES



15 Minute Break


Managing Information Flow & Decision Making



Set Based Design


- Method that keeps requirements and options flexible for as long as responsible during the development process.
- Highly collaborative and less rework during design
- Allows for:
 - Designers to be more creative
 - Owners to get more options and more information to inform decisions
 - Builders get involved earlier to inform cost, schedule, and constructability

Set Based Design



Set Based Design

Also known as
Set Based
Concurrent
Engineering



Improving complex systems today : proceedings of the 18th ISPE International Conference on Concurrent Engineering,
Massachusetts, USA 4-8 July 2011, pp433-430 Eds. Daniel D Frey, Shuichi Fukuda, Georg Rock.

Tools Supporting Set Based Design

A3 Report Name

1. Background

- Importance
- Context

5. Countermeasures

- Possible Solutions
- Go Back to Goals and Add Details If Needed

2. Current Situation

- Problem Statement
- Process Mapping

6. Implementation

- List of Actions
- Assign Responsible Individuals

3. Set targets/goals

- Desired Outcome
- Success Metrics

7. Follow-Up

- Report Results
- Standardize or Modify

4. Root Cause Analysis

- 5 Whys
- Dig Deeper
- Find Initial Problem

Project Leader:

Team Members:

Department:
Date:

Choosing by Advantages (CBA)

- Decisions must be based on **Differences**
- Decisions must be based on the **Importance of Advantages**
- Decisions are **Anchored** to the relevant facts
 - * **Stakeholders** contribute relevant **subjective** data



Set Based Design Examples


		Category 1: Missing Influence	Category 2: Planning Influence	Category 3: Means & Methods	Study Go No Go	Construction savings (\$)	Design cost impact (\$)	LRM for decision	Construction savings (weeks)	Design schedule impact	RECOMMENDATION	Core team
												TEAM / notes
STRUCTURE												
SidePlate Steel Frame Connection (Structure)	STRUCTURE (Structure)							DD-1				Schedule Advantage, vet cost& Detail
Connect X Tech (Structure)	STRUCTURE (Structure)							N/A				
Concrete Strut Inserts	STRUCTURE (Structure)							DD-3 BCS				Coord. Big items bigger than 4" dia
Structural Bays (Connected on the Ground)	STRUCTURE (Structure)							M&M				
Anchors in Slab (Structure)	STRUCTURE (Structure)							M&M				
Rebar Cages for Foundation Walls (Structure)	STRUCTURE (Structure)							M&M				
INTERIORS												
bathroom pods (with structure) 6 sided box	PODS (Interiors)							SD-3 BCS				Slab Thickness is a project constraint , need to be roll in showers(5 sided box)/ Panels / might have to provide FP
bathroom panels (5 sided box) no floor	PANELS (Interior)							DD-2 INT				
Prefinished 15'X15'X60' volumes (mods)	MODS (Interiors)											
OR Room Ceilings (Cleansuite)	FRAMING (Interiors)							DD-1 Int				Coordinate w/ Facilities / Future Flexibility
Pharmacy Clean Room	FRAMING (Interiors)							DD-2 Int				Pharmacy Team Is Interested in Clean Room
OR Panelized Room	PANELS (Interior)											More Information/Installed Location quantities
Infrastructure Room (MODS)	MODS (Interior)							SD-3 Int				Need to understand Design / Finish Understanding/ accoustics
PreManufactured Headwalls	PANELS (Interior)							SD-3 Int				
Pre-Built Headwalls (Multi-Trade) WT/PJD Prefab	PANELS (Interior)							DD-2 Int				
Electrical Closet Pods	PODS (Interiors)							SD-3 Int				Panels or Boxes
IT Closet Pods	PODS (Interiors)							SD-3 Int				Panels or Boxes
Prefabricated Soffits	FRAMING (Interiors)							M&M				Curve Building is a challenge
Interior Panel System (DiRT) Ki								DD-1 Int				
Interior wall panels (Multi-Trade) (WT/PJD Prefab)	PANELS (Interior)							M&M				
Off the shelf Interior Finish Products	FINISHES (INTERIOR)											




Set Based Design Example


										Core team									

Decision Flow Model




Decision Flow Model





[illegible]

Decision Flow Model



Decision Flow Model

PROBLEM STATEMENT				ROOT CAUSE ANALYSIS / INTENDED GOAL				<div>A3-018 NICU Layout Spring Valley Hospital Addition Date: 7/14/2015 Author: Bill Whipple</div>	
The original business case for NICU II to expand by 2 bassinets to a total of 11. This A3 is to explore the value of Option 2 in comparison to currently baseline Option 1 for the purpose of increasing project value. The existing NICU waiting room is a code required space and provides the functional need to secure visitor access to all NICU spaces.				Reduce the current NICU remodel budget of Option 1 (\$311,589) by (-\$15,247) and increase value. The reduction in this remodel scope is part of a strategy to bring total project cost, lower addition and remodel scope, into budget alignment. The initial goal of providing 11 bassinets does not work with current 3:1 nursing ratios. Goals is to increase the number of bassinets to 12. Each bassinet is equal to roughly \$45,000 per month. Reduce construction duration and disruption of babies.					
OPTION 1 (Baseline)				OPTION 2				ADDITIONAL VALUE	
11 Bassinets				12 Bassinets				Item	Cost
								Relocate medication dispensing to open	\$4,416
								Medication room to formula prep	No Cost
								Panic button at nurse station	\$5,375
								Prefab stud walls to reduce duration	\$0
								Create equip. storage room nearby	\$13,500
								Sound blankets above ceiling	\$2,700
								Remove walls isolation Bay 1	\$4,789
								Upgrade acoustics of ceiling tiles	\$18,025
								Alphone at Nurse Station	\$2,240
								Eliminate new VAV for Med-Room	\$0
								Create wellness office nearby	\$9,000
								RECOMMENDATION	

Decision Flow Model



1 PROBLEM STATEMENT		2 ROOT CAUSE ANALYSIS / INTENDED GOAL	
Explore solutions to relocate and expand the inpatient Pharmacy department and corresponding services. The Materials Management department is expanding into the existing Pharmacy. The existing inpatient Pharmacy department is 2,452 SF included sterile compounding, Pyxis refill, crash cart refill, unit dose, offices, breakdown, and bulk storage. No cyclic compounding services are currently provided. The median average area for an inpatient pharmacy is 15 SF/bed. There are currently 237 beds SVH or 10.3 SF/bed. This project includes +54 beds to 291 total. The next tower build-out +90 beds to 381 total. Two pharmacists are deployed.		Sterile compounding area to become USP 797 compliant. Breakdown and bulk storage separate from fill area. Add 2 private offices and clinical pharmacist workstation Accommodate Pharmacy program of 3,731 DGSF or better Keep projects costs and remodel areas to a minimum Maintain security and patient services relationships	


A3-001
Pharmacy Relocation
Spring Valley Hospital Addition
Date: 2/11/2015
Author: Bill Whipple

3 CRITERIA	OPTION A	OPTION B	OPTION C
	Existing Administration, HR, Computer Training	Existing Physician Lounge, Medical Records, Misc offices	Existing CVO office, Computer Training, and Risk
PROJECT AREAS Less required space in new tower, better Less remodel space, better Less shell space, better	BEST 4,869 SF to new tower 5,136 SF of existing building remodel 800 SF of shell space (10,805 SF total impact)	GOOD (1,499 SF total impact difference) 3,660 SF to new tower 8,644 SF of existing building remodel 0 SF of shell space (12,304 SF total impact)	BETTER (+237 SF total impact different) 4,280 SF to new tower 6,762 SF of existing building remodel 0 SF of shell space (11,042 SF total impact)
PHARMACY AREA More space, better	BETTER 4,300 DGSF	BEST 4,600 DGSF	GOOD 3,900 DGSF
WORK FLOW More rectangular department, better Less access from public corridors, better	GOOD Height:width ratio 1:3.7, three distinct appendages 1 public corridor egress door	BEST Height:width ratio 1:1, one distinct appendage 0 public corridor egress doors	BETTER Height:width ratio 1:1.26, no appendages 0 public corridor egress doors
OPERATIONAL IMPACT Less departments moved, better Right sized departments, better Less total department reduction, better	BEST 5 departments impacted 1 department reduced in size (9.5% reduction in Computer Training)	GOOD 6 departments impacted 2 departments reduced in size (9.3% reduction in Doctor's Lounge) (60.9% reduction in Medical Records) (No increase in Human Resources area)	BETTER 7 departments impacted 2 departments reduced in size (9.5% reduction in Computer Training) (28.8% reduction in CVO Office)
CONSTRUCTION AND DESIGN IMPACT Less phases, better Less building systems changes better	GOOD 3 phases Pharmacy under floor drain leaks Venting to roof not very feasible	BEST 3 phases Pharmacy under single story portion of building Misc offices under floor drain leaks	BETTER 3 phases Most of pharmacy under single portion of building Human Resources under floor drain leaks
COST* Less construction cost, better \$155 / SF for tenant improvement \$170 / SF for major remodel \$65 / SF for minor remodel Pharmacy location multiplier *These costs are for decision making magnitude only, not final costs	BETTER \$1,601,790 rough construction cost 4,869 SF of tenant improvement 4,516 SF of major remodel 620 SF of moderate remodel 1.025	GOOD \$1,701,000 rough construction cost 4,460 SF of tenant improvement 4,600 SF of major remodel 3,244 SF of minor remodel 1.01	BEST \$1,584,430 rough construction cost 5,080 SF of tenant improvement 3,900 SF of major remodel 2,062 SF of minor remodel 1.00
OTHER CRITERIA			

4 RECOMMENDATION	5 IMPLEMENTATION PLAN	CORE GROUP APPROVAL SIGNATURES:																																	
Recommend Option C with understanding that the cost of the Pharmacy relocation must come down. The project budget was set at \$1.5M in construction cost for Pharmacy, Materials Management, and Kitchen. Option C provides a balanced solution to the expansion of a few department while meeting the programmed area for Pharmacy done with Milan Monclovich and James Pickren.	<table border="1"> <thead> <tr> <th>Action Item</th> <th>Champion</th> <th>Completion Date</th> </tr> </thead> <tbody> <tr> <td>Revise costs</td> <td>Katie Wells</td> <td>February 18, 2015</td> </tr> <tr> <td>Generate Pharmacy sketch</td> <td>Bill Whipple</td> <td>February 24, 2015</td> </tr> <tr> <td>Draft First Floor Tower floor plan</td> <td>Bill Whipple</td> <td>February 18, 2015</td> </tr> <tr> <td>Finalize Administration department</td> <td>Bill Whipple</td> <td>February 20, 2015</td> </tr> <tr> <td>HR, CVO, Risk sketches</td> <td>Bill Whipple</td> <td>February 24, 2015</td> </tr> </tbody> </table>	Action Item	Champion	Completion Date	Revise costs	Katie Wells	February 18, 2015	Generate Pharmacy sketch	Bill Whipple	February 24, 2015	Draft First Floor Tower floor plan	Bill Whipple	February 18, 2015	Finalize Administration department	Bill Whipple	February 20, 2015	HR, CVO, Risk sketches	Bill Whipple	February 24, 2015	<table border="0"> <tr> <td>Leonard Freehof</td> <td>_____</td> <td>Date: _____</td> </tr> <tr> <td>Matthew Wheelus</td> <td>_____</td> <td>Date: _____</td> </tr> <tr> <td>Tara Laski</td> <td>_____</td> <td>Date: _____</td> </tr> <tr> <td>Douglas Lee</td> <td>_____</td> <td>Date: _____</td> </tr> <tr> <td>Stan Chiu</td> <td>_____</td> <td>Date: _____</td> </tr> </table>	Leonard Freehof	_____	Date: _____	Matthew Wheelus	_____	Date: _____	Tara Laski	_____	Date: _____	Douglas Lee	_____	Date: _____	Stan Chiu	_____	Date: _____
Action Item	Champion	Completion Date																																	
Revise costs	Katie Wells	February 18, 2015																																	
Generate Pharmacy sketch	Bill Whipple	February 24, 2015																																	
Draft First Floor Tower floor plan	Bill Whipple	February 18, 2015																																	
Finalize Administration department	Bill Whipple	February 20, 2015																																	
HR, CVO, Risk sketches	Bill Whipple	February 24, 2015																																	
Leonard Freehof	_____	Date: _____																																	
Matthew Wheelus	_____	Date: _____																																	
Tara Laski	_____	Date: _____																																	
Douglas Lee	_____	Date: _____																																	
Stan Chiu	_____	Date: _____																																	




Decision Flow Model



Utilizing LPS® in Work Clusters


Develop the Plan



Execute the Work

Decision Mapping and Pull Planning

Traditional Design Planning vs. Target Value Delivery Approach



Managing by “Big Bars”

Detailed Plan

File Automation Forms Connections Wake Forest Pull Plan ☆

Grid View Interiors Arial 10 B I U G A A

Cluster Team/PT/Resp	Task Name	Committed By	Status	Comple... as Planned	Du...	Start	Finish
645 Interiors	Interior Lobby Approval after VE Decisions	Bill Payne	Milestone	<input type="checkbox"/>	10d	05/01/23	05/12/23
652 Interiors	ED Patient registration network based on backfill meeting comments	Amanda Brooks	In Progress	<input type="checkbox"/>	20d	06/26/23	07/21/23
657 Interiors	BOS provide pricing for Pauldault floors	Lauren Edwards	In Progress	<input type="checkbox"/>	21d	07/26/23	08/23/23
664 Interiors	David Sheehan review of LS plans, specifically around flammable substances in I	Amanda Brooks	Not Started	<input type="checkbox"/>	21d	08/04/23	09/01/23
668 Interiors	Analyze door hardware for Assa Abloy	achahulski@opti	In Progress	<input type="checkbox"/>	6d	09/18/23	09/25/23
669 Interiors	CPL markups to SSR to meet DD deadline	Amanda Brooks	<input type="checkbox"/>	<input type="checkbox"/>	1d	09/01/23	09/01/23
670 Interiors	Receive Door Hardware back from Assa Abloy	achahulski@opti	Not Started	<input type="checkbox"/>	1d	09/11/23	09/11/23
671 Interiors	Import door hardware into revit model	achahulski@opti	Not Started	<input type="checkbox"/>	1d	09/11/23	09/11/23
674 Interiors	Issue Phase 2 DD to BOS	achahulski@opti	Not Started	<input type="checkbox"/>	1d	09/14/23	09/14/23
675 Interiors	Issue Phase 2 DD to DHR	achahulski@opti	Not Started	<input type="checkbox"/>	1d	09/14/23	09/14/23
682 Interiors	Engage DHR to review phase 2	achahulski@opti	Not Started	<input type="checkbox"/>	1d	11/14/23	11/14/23
684 Interiors	Lao Casework Vendor Drawings	achahulski@opti	Not Started	<input type="checkbox"/>	1d	11/17/23	11/17/23
685 Interiors	Initial Coordination - Furniture RFP	Molly Livingstone	Not Started	<input type="checkbox"/>	20d	12/11/23	01/05/24
688 Interiors	Write Furniture RFP	Molly Livingstone	Not Started	<input type="checkbox"/>	40d	01/22/24	03/15/24
690 Interiors	Furniture RFP Responses due back	Molly Livingstone	Not Started	<input type="checkbox"/>	1d	04/25/24	04/25/24
691 Interiors	CD BIM submission	Adam Chahulski	Not Started	<input type="checkbox"/>	1d	04/26/24	04/26/24
693 Interiors	Response Review/Interview/Award Furniture	Molly Livingstone	Not Started	<input type="checkbox"/>	10d	05/10/24	05/21/24
694 Interiors	Issue Furniture PO	Molly Livingstone	Not Started	<input type="checkbox"/>	1d	05/24/24	05/24/24
702 Interiors	Conference Room Configuration - Meditation Space	Bill Payne	<input type="checkbox"/>	<input type="checkbox"/>	1d	09/24/23	09/24/23
703 Interiors	Whispering VE Item	Jesse Regan	<input type="checkbox"/>	<input type="checkbox"/>	1d	09/24/23	09/24/23
704 Interiors	Lobby Room layout	Bill Payne	<input type="checkbox"/>	<input type="checkbox"/>	1d	09/31/23	09/31/23
705 Interiors	Pediatrics user changes	Amanda Brooks	<input type="checkbox"/>	<input type="checkbox"/>	8d	09/23/23	09/01/23
706 Interiors	TDR Electrical Rooms	mcaidwell@opti	<input type="checkbox"/>	<input type="checkbox"/>	1d	09/31/23	09/31/23
707 Interiors	Begin Matching/Coordinating Lights with WSP	mcaidwell@opti	<input type="checkbox"/>	<input type="checkbox"/>	1d	09/25/23	09/25/23

Decision Mapping and Pull Planning

Identify Major Decisions vs. Depending on Traditional Design Milestones

Schematic Phase	Sequence	Decisions	Facilitator	Needs	Notes
	9	Emergency Power	Electrical Eng	emergency business functions	
	10	Future Expansion Needs			Structural, utility & adjacencies considerations
	11	Access Control	Communications Designer	depending on complexity of need for facility	
	12	Low Voltage Systems	Communications Designer		
	13	Partition Types	Architect	acoustical designer helping with STC ratings & guidelines	
	14	Location on Property	Architect, Civil Eng	existing utilities, flood planes, future growth needs, preliminary geotech information	structure alignment on site
	15	Geotechnical Data & Analysis	Geotech Eng		
	16	Finish Floor Elevation	Civil Eng, Architect	contractor input on site leveling, means & methods, borrow/export needs	
	17	Parking	Civil Eng	specialty consultant (especially where pkg decks considered)	
	18	Outdoor Amenities	Landscape Arch, Arch		
	19	Structural Frame System	Structural Eng	contractor input on market economy & means/methods	
	20	Structural Layout & Spacing	Structural Eng, Arch		
	21	Foundation System	Structural Eng, Geotech		
	22	HVAC System	Mech Eng	contractor input on market economy & maintenance, facilities input, energy consumption consultant	
	23	Plumbing & Electrical Programmatic Fixture Needs	Mech & Elect Eng, Arch, Interior Arch		counts and level of finish
	24	Redundancy Needs	Mech & Elect Eng	input from facilities, contractor input on market & m/m	
	25	Major Eq Placement	MEP & Arch		
	26	Single Line Electrical Design	Electrical Eng		
	27	Interstitial Needs (abv clg & below fir)	MEP & Arch		
	28	Programmatic Finishes	Interior Design	owner influence	ie: allotment of hard fir vs soft vs resilient, etc
	29	Glazing & Veneers: % of Openings	Arch, Mech Eng	contractor input on cost allotments, energy consumption consultant	



Decision Mapping and Pull Planning

Identify Major Decisions vs. Depending on Traditional Design Milestones

Preconstruction & Design Milestone Mapping											
Major Decision Milestones	PROGRAM	PROGRAM SIZING	ORIENTATION	LOCATION	FRAME	FOUNDATION	MECHANICAL	ENVELOPE	POWER	FIXTURES	FINISHES
	<div><div></div><div>Floor Plate Locked 90%</div><div></div><div>Floor Plate Locked 100%</div><div></div></div>										
	<ul style="list-style-type: none">Department Needs IdentifiedDepartment Adjacency Requirements	<ul style="list-style-type: none">Space Allocation ProgramCode & Licensure Requirements	<ul style="list-style-type: none">Building ShapeNumber of Levels vs Footprint	<ul style="list-style-type: none">Building Location on propertySite Design Elements	<ul style="list-style-type: none">Structural Frame TypeStructural Layout & SpacingStructural Interstitial	<ul style="list-style-type: none">Foundation TypeGeotechnical Information	<ul style="list-style-type: none">HVAC System SelectionMajor Equipment PlacementUtility Routing	<ul style="list-style-type: none">Roof TypeStorm SystemInsulation LevelWindows & Veneers	<ul style="list-style-type: none">Roof TypeStorm SystemInsulation LevelWindows & Veneers	<ul style="list-style-type: none">Plumbing FixturesLight FixturesFFE	<ul style="list-style-type: none">Level of FinishesReflective CeilingAccess ControlMillworkLow Voltage Layout
	<ul style="list-style-type: none">OwnerProgram Manager	<ul style="list-style-type: none">OwnerProgram ManagerDesignerBuilder	<ul style="list-style-type: none">OwnerProgram ManagerDesignerBuilderStructural Expert	<ul style="list-style-type: none">OwnerProgram ManagerDesignerBuilderStructural ExpertCivil Expert	<ul style="list-style-type: none">OwnerProgram ManagerDesignerBuilderStructural Expert	<ul style="list-style-type: none">OwnerProgram ManagerDesignerBuilderStructural ExpertCivil Expert	<ul style="list-style-type: none">OwnerProgram ManagerDesignerBuilderMechanical Expert	<ul style="list-style-type: none">OwnerProgram ManagerDesignerBuilderWalls Expert	<ul style="list-style-type: none">OwnerProgram ManagerDesignerBuilderElectrical Expert	<ul style="list-style-type: none">OwnerProgram ManagerDesignerBuilderElectrical ExpertMechanical ExpertInteriors Design	<ul style="list-style-type: none">OwnerProgram ManagerDesignerBuilderWalls ExpertFlooring ExpertMillwork ExpertDoor ExpertInteriors Design
	<ul style="list-style-type: none">Financial Pro-FormaBench Marking against similar Projects for Investment PredictionsEstablish Initial Target	<ul style="list-style-type: none">Want vs Need AnalysisBudgeting Validation & Feasibility	<ul style="list-style-type: none">Budgeting Validation & FeasibilityDesign Set Selection (CBA)Document & Share (Design Update & A3)	<ul style="list-style-type: none">Budgeting Validation & FeasibilityDesign Set Selection (CBA)Document & Share (Design Update & A3)	<ul style="list-style-type: none">Budgeting Validation & FeasibilityDesign Set Selection (CBA)Document & Share (Design Update & A3)	<ul style="list-style-type: none">Budgeting Validation & FeasibilityDesign Set Selection (CBA)Document & Share (Design Update & A3)	<ul style="list-style-type: none">Budgeting Validation & FeasibilityDesign Set Selection (CBA)Document & Share (Design Update & A3)	<ul style="list-style-type: none">Budgeting Validation & FeasibilityDesign Set Selection (CBA)Document & Share (Design Update & A3)	<ul style="list-style-type: none">Budgeting Validation & FeasibilityDesign Set Selection (CBA)Document & Share (Design Update & A3)	<ul style="list-style-type: none">Budgeting Validation & FeasibilityDesign Set Selection (CBA)Document & Share (Design Update & A3)	<ul style="list-style-type: none">Budgeting Validation & FeasibilityDesign Set Selection (CBA)Document & Share (Design Update & A3)
	<div><div></div><div>CONTINUOUS ESTIMATING AND INNOVATION</div><div></div></div>										

Integration Event



From CPR Program

Cluster Work Activity

- Cluster Assignments
- Brainstorm Value Driving Ideas within your Cluster
- Write 1 idea per sticky note
- Ideas that could optimize owner value
(Value Def & CoS)
- Analyze and Agree on Top 3 to present at Core Team / Integration Event

30 MINUTES

Cluster Work Presentations



- Present Top Value Ideas to Core Team
- Recommendation for Implementation
- Core Team Decision for Further Evaluation

15 MINUTES

Cluster Maintenance

- Be nimble based on project needs
- It's ok to close out a cluster team when necessary
- Check in with cluster team on effectiveness occasionally



Drive Learning & Improvement



Discussion Question



What new actions or ideas that you learned today can you take back to your project?

Learning Objectives



Discover how to effectively organize and manage teams in cross functional, interconnected work clusters and how cluster groups engage with cost model and Last Planner System in Design.



Discover the importance of key leadership roles and responsibilities that are foundational to the successful implementation of Target Value Delivery, information management, and decision making.




Identify what are the characteristics of effective facilitation and Lean practices at a project and work cluster level for Target Value Delivery to support information flow.




Understand information and decision-making workflow across clusters and from cluster groups to decision making authorities within team and how to managing owner prerogative in the context of consensus driven decision making.

Lean Journey to Mastery

How will you reach the next level on your journey?




Define Your Journey



eLearning Courses

- Introduction to the Last Planner System®
- Introduction to Lean Project Delivery
- Lean in the Design Phase
- Effective Big Room
- Target Value Delivery
- Last Planner System® in Design



Questions?





Conduct Plus/Delta



Plus: What produced *value* during the session?



Delta: What could we *change to improve* the process or outcome?

+	▲

Presenter Contact Information




Julie Glassmeyer
Owner
Glassmeyer Construction Consulting &
Coaching, LLC



Michelle Whiteside
Regional Lean Director
Brasfield & Gorrie

LCI Website Information



www.LeanConstruction.org



Rate Session In Event App

Plan to evaluate
each session you
attend in the
event mobile app!

