

26<sup>TH</sup> ANNUAL



26<sup>TH</sup> LCI CONGRESS  
OCTOBER 22-25, 2024

# Manpower Boards for Specialty Trade Contractors

Chris Watne – KHS&S Project Superintendent

**SURFING THE WAVE OF LEAN DESIGN AND CONSTRUCTION**

October 24<sup>th</sup>, 2024

# The Why

- To create a plan to facilitate next week's work and discuss any needs surrounding it.
- Getting information from the Pull plan into an executable WWP and assigning resources is a difficult but crucial part of creating productive flow.
- Not knowing if there is enough available work for the amount of manpower on the project.
- Often times we struggle to know what the plan is.

# Daily Meetings

---

- When and Who:
  - Daily morning huddle with field leadership
  - Before work
  - 20-30 Mins
  - Fits around project start time



# Daily Meetings

---

- What:
  - Walking through plan for the day
    - Manpower Board
  - Constraints that could interfere with our plan
  - Coordinate inspections
  - Update our material delivery board
  - Go over needs for the day
  - Open discussion





# Daily Cont.

MATERIAL DELIVERIES/  
STOCKING

9/19 - THURS - JAMB PICK UP FROM RANCHO  
 9/20 - FRI - JAMB DELIVERY/STOCKING  
 - 7:00 AM FIRE ROAD W/ CRANE  
 9/20 - FRI - STOCKING MATERIAL/REPLACEMENT TRACK  
 9/24 - TUES - EAST JAMB MATERIAL

RFI NEEDS

WIFI:  
 NAME: VERIZON\_7QZHX9  
 PASS: nape-mono3-fig (lowercase)

MANPOWER  
 - CHRIS ANDERSON

Chris

- Co-ordinate w/Elizabeth  
 Shop Drawings

CONSTRAINTS

- HM DOOR FRAMES 9/27 PER SCHEDULE  
 - ROLL UP DOOR SHOPS FRAMING 9/25  
 - CORNER COLUMN HST

SAFETY

\* - HOT WORK PERMITS  
 - SET UP SITE GROUP TEXT  
 - INTERNAL  
 - WITH PCL  
 - 100% SAFETY FOCUS  
 - STEEL TOE BOOTS  
 - PCL ORIENTATION FROM PREVIOUS PROJECT

MIKEY

NEEDS

- SCAFFOLD USER CONF  
 - LAZER GC PROGRAM  
 - ROLL UP DOOR SHOPS EAST/WEST  
 - HM DOOR FRAMES

NON NEGOTIATIONS

- DAILY STAND UP MEETING  
 - THURS PLANNING MEETING  
 - PRODUCTION TRACKING - PROCORE  
 - Bi-Weekly "Red/Yellow/Green"  
 - DAILY SCAFFOLD INSPECTIONS - SMARTSHEET QR  
 - MANPOWER ACCOUNTABILITY

ESTEVAN

CJ

JEFF

WOOD BLOCKING  
 W/IN DETAIL



Agenda:

- 
- WHITEHOUSE FENCE
- BOUSER JR
- THOMPSON INTERIOR
- MINES INTERIOR
- EXIT TUNNEL
- PEACH'S CASTLE
- PEACH'S CASTLE INTERIOR
- ENTRY AREA
- RETAIL BLOCK
- NAPT TIPS
- MISC
- MEET + GREET
- MK CLOUDS



# Manpower Demonstration

KH  
S&S

1-3-1  
MINDSET

Problem

Solution

Action

Plaster Team Weekly Plan						
Team	Monday 10/17	Tuesday 10/18	Wednesday 10/19	Thursday 10/20	Friday 10/21	Weekend 10/22
PET YELLOW GREEN	- Y/N	- Y/N	- Y/N	- Y/N	- Y/N	- Y/N
PINEDO / CARLOS	FRAME CORNER COLUMNS 21000-0513 Y/N	- Y/N	- Y/N	- Y/N	- Y/N	- Y/N
OTTO / LUIS	FRAME EAST LOWER 22000-0503 Y/N	- Y/N	- Y/N	FRAME WEST UPPER 24000-0503 Y/N	- Y/N	- Y/N
JESSE	INSTALL HOLIDAY HOOK BACKING 21001-0504 Y/N	- Y/N	- Y/N	FRAME WEST UPPER 24000-0503 Y/N	- Y/N	- Y/N
CHRISTINA / SOEY	FRAME INTERIOR A-D 31000-0503 Y/N	- Y/N	- Y/N	- Y/N	- Y/N	- Y/N
CHRIS A.	HOLIDAY HOOK LAYOUT 21001-0501 Y/N	LAYOUT EXTERIOR WALLS 20000-0501 Y/N	- Y/N	LAYOUT INTERIOR WALLS 30000-0501 Y/N	- Y/N	- Y/N
	- INTERIOR MATERIAL NORTH WALLS Y/N	- WATERPROOFING Y/N	- Y/N	- SOUTHWEST 3/Y/N	- Y/N	- Y/N
	- Y/N	- Y/N	- Y/N	- Y/N	- Y/N	- Y/N
	- Y/N	- Y/N	- Y/N	- Y/N	- Y/N	- Y/N
	- Y/N	- Y/N	- Y/N	- Y/N	- Y/N	- Y/N



PRODUCTION MANAGER'S WEEKLY WORK PLAN ( WWP )																														
Customer Name:		Week Ending <div>Key: Input Plan Info Calculation done for you Complete at close of day/week</div> 11/1/2024					Hours Required for Planned Production		Hours Required for Actual Production		Approved by GC Representative:			CATEGORIES OF VARIANCE																
Project Name: USH P409 Fast & Furious							Should Use	0	Should Have Used	0	CJ Gohl		1	UNSAFE CONDITION	5	EQUIP/HOISTING	9	STRUCTURAL	13	PLUMBING										
Project Number: 16558-14							Plan to Use	240	Did Use	0	Signature:	Date:	2	WEATHER	6	RFI/SUBM/SHOP	10	CONCRETE	14	INSP/PERMIT										
Project Location: Universal City, CA							Total Production Goal for Week KEY (Adjustable)							3	LABOR	7	INTEREF - KHS&S	11	MECHANICAL	15	SCAFFOLD									
Senior Field Rep Name: Chris Watne							% 97.5% 95.0% UNDER							4	MATERIALS	8	CO/HOLD/STOP	12	ELECTRICAL	16	0									
Project Manager Name: CJ Gohl																														
Task Made Ready?	TASK DESCRIPTION Example: Location (Floor 4) / Task (Framing, Drywall) / Specific Location (gridline or room #)	Current Constraint	Foreman Team #	Cost Code (If EWA, select "EWA" from list)	Sub Task Name	Use Total Work Remaining? (Y/N)	Work Remaining UOM	Unit of Measure	Hours Remaining	Total Production GOAL	Actual Production for the Week	Total expected hours each day						Planned Hours	Calculated Hourly Prod Rate	Calculated Daily Team Production	Material (type and quantity) needed for task	"X" Ordered?	"X" Delivered?	"X" In Place?	Total Hours Used	Actual Hourly Prod Rate	Task Completed as Met Current Production	Reason for Variance	Category	
												%	uf/reb/rtk	uf/reb/rtk	SUGGESTED	Mon	Tues													Wed
	Frame North Elevation Exterior		Watne - Pinedo / Carlos	21000-0503		Y		LF		30		2	2	2				48		10		X	X	X						
	Hang North Elevation Exterior		Watne - Pinedo / Carlos	21000-0521		Y		SQFT		2240					2	2		32		1120		X	X	X						
	Frame 1st Floor North Interior		Watne - Otto / Luis / Chris	30000-0503		Y		LF		360		3	3	3	3			96		90		X	X	X						
	Hang Top Out 1st Floor Interior		Watne - Otto / Luis / Chris	30000-0587		Y		SQFT		960						3		24		960		X	X	X						
	Install Door Frames 1st Floor		Watne - Jesse / Brandon	30000-0574		Y		Each		35		1	1	1	1	1		40		7		X	X	X						
						Y																								
						Y																								
						Y																								
						Y																								





# Wins

---

- Communicating constraints that can hold up our work
- Understanding where all manpower is going to be working and ensuring we are not over staffed
- Knowing that all team members are on the same page
- Assuring we don't have equipment on site that is not being used
- Checking in with the foreman to make sure material is at Point of use
- Ensuring that the plan matches the budget

# Lessons Learned

---

- Spot check that the team is following the plan and has material at point of use
  - Both Daily and Weekly
- Challenging the foreman to plan for the appropriate amount of time needed for a task
- Keep everyone on track - Side conversations can start easily and be disruptive
- Have a list of milestones prior to meeting each week

# Questions?







26<sup>TH</sup> LCI CONGRESS  
OCTOBER 22-25, 2024



In the spirit of continuous improvement, we would like to remind you to complete this session's survey! We look forward to receiving your feedback.

# Contact Us

---

**Chris Watne**

KHS&S Contractors

Chris.Watne@khsswest.com

---







26<sup>TH</sup> LCI CONGRESS  
OCTOBER 22-25, 2024

Thank you for attending this presentation. Enjoy the rest of the 26<sup>th</sup> Annual LCI Congress!



# Icon Library

- These icons can be used throughout your presentation



Plan | Value  
Generation



Do



Check



Act | Safety



Continuous  
Improvement



Respect for  
people | Team



Removal of  
Waste



Process  
and Flow



Optimize the  
Whole



Built  
Environment



Tools



Resources



Training



Research



Collaboration



Emphasis

